

कार्यालय जोधपुर विकास प्राधिकरण, जोधपुर

क्रमांक :- 724

दिनांक : 7-7-21

-:: सीमित निविदा ::-

जोधपुर विकास प्राधिकरण, जोधपुर में निम्नलिखित कार्य हेतु संबंधित कार्य में कार्यरत पंजीकृत प्रतिष्ठानों/संवेदको/फर्मों से सीमित निविदा के माध्यम से बंद लिफाफे में दरे आमंत्रित की जाती है।

क्र. स.	कार्य का नाम	अनुमानित लागत (लाखों में)
1.	जेडीए घरिसर स्थित आयुक्त कार्यालय में रंग रोगन, दरवाजे, फॉल्स सिंलिंग व अन्य मरम्मत कार्य।	1.76 लाख

शर्त :-

1. निविदादाता द्वारा प्रस्तुत की जाने वाली दरें समस्त करो सहित प्रस्तुत करनी होगी।
2. अन्य शर्तें एवं अनुसूची इत्यादि कार्यालय समय में प्राप्त की जा सकती हैं।
3. पेन कार्ड एवं जीएसटी की स्वप्रमाणित प्रति प्रस्ताव के साथ संलग्न करना अनिवार्य होगी।
4. निविदादाता दिनांक 13.07.2021 को दोपहर 2.00 बजे तक प्राप्त की जाकर उसी दिन दिनांक 13.07.2021 को सायं 4.00 बजे खोली जायेगी।

अधिसाषी अभियंता (जोन -मुख्यालय)
जोधपुर विकास प्राधिकरण, जोधपुर
दिनांक :

क्रमांक :

प्रतिलिपि निम्नलिखित को सुचनार्थ प्रेषित है :-

1. एनालिस्ट कम प्रोग्रामर, जोधपुर विकास प्राधिकरण, जोधपुर को मय निविदा के प्रेषित कर लेख है कि कृपया संलग्न समिति निविदा www.sppp.raj.nic.in की वेबसाईट पर तुरन्त प्रदर्शित करे।

अधिसाषी अभियंता (जोन -मुख्यालय)
जोधपुर विकास प्राधिकरण, जोधपुर


JODHPUR DEVELOPMENT AUTHORITY, JODHPUR

PWD Building BSR 2019


ESTIMATE

र्य का नाम :- जेडीए परिसर स्थित आयुक्त कार्यालय में रंगरोगन, दरवाजे, फाल्स सिलिंग व अन्य मरम्मत कार्य।

No.	BSR	Item	Qty.	Unit	Rate In Rs.	Amount
1	14.39	Dismantling wooden boards in lining of walls and partition excluding supporting members but including stacking within 50 meter lead : Thickness above 10 mm up to 25mm.	50.00	Sqm.	28.00	1400.00
2	14.61	Dismantling aluminium / gypsum partitions, doors, windows, fixed glazing and false ceiling incl. disposal of unserviceable material and stacking of serviceable material within 50mtr lead as directed by Engineer in charge.	44.00	Sqm.	5.50	242.00
3	1.39	Providing and injecting Chloropyrifous Emulsifiable concentrate 20 % with 1 % concentration for PRE-CONSTRUCTIONAL Anti termite treatment as per IS 6313 part III and amended from time to time and creating a continuous chemical barrier under and around the column pits, wall trenches, basement excavation, top surface of plinth filling, junction of wall and floor along the external perimeter of building expansion joints, over the top surface of consolidated earth of which aproch is to be laid surrounding of pipes and conduits etc. complete as per specification (Plinth floor area only shall be measured for payment)	135.00	Sqm.	504.00	68040.00
4	12.6	Applying plaster of Paris over cement plaster surface for making even surface.	85.00	Sqm.	154.00	13090.00
5	R-7.6	Painting two coats after filling the surface with synthetic enamel paint in all shades on plastered concrete surfaces as per MORTH specifications Cl. 803. New Surface	342.00	Sqm.	94.00	32148.00
6	8.20.5	Providing and fixing factory made solid core single leaf Door shutter made out of composite ECO friendly wood laminated with 0.8 mm thick polymer termite and water resistant fire retendent technology, gluing by vacuum lamination technology various premoulded design on both face as per IS-2202 (Part-I) 1991 (Door fitting shall be supplied by the department) 35mm thick (2100mmx900mm size)	3.00	Nos.	7696.00	23088.00
7	8.19.5	Extra in flush doors for providing vision panel of size 15x15 Cm. square or 15 Cm dia.	3.00	Nos.	150.00	450.00
8	10.4	Providing and Fixing at all height all false ceiling of 12.5 mm thick tapered edge Gypsum board conforming to IS : 2095 including providing and fixing of frame work made of special section power pressed from M.S. sheet and galvanized in accordance with zinc coating 600 as per IS : 277 and consisting of angle cleats of thick 25 mm wide x 16 mm thick with flanges of 22 mm and 37 mm at 1200 mm center to center one flange fixed to the ceiling with dash fastener 12.5 mm dia x 40 mm long with 6 mm dia bolts to the hangers of 25x25x5mm of required length, and other end of angle hanger being fixed with nut and bolts to G.I. channels 45 mm x 15 mm x 0.9 mm running at the rate of 1200 mm center to center to which the ceiling section 0.5 mm thick bottom wedge of 80 mm with tapered flanges of 26 mm each having clips of 10.5 mm at 450 mm center to center shall be fixed in a direction perpendicular to G.I. channel with connecting clips made out of 2.64mm dia x 230mm long G.I. wire at every junction including fixing the gypsum board with ceiling section and perimeter channels 0.5mm thick 27 mm high having flanges of 20 mm and 30 mm long, the perimeter of ceiling fixed to wall / partition with the help of rawl plugs at 450 mm center to center with 25 mm long drive-all screws @ 230mm interval including jointing and fixing to a flush finish of tapered and square edges of gypsum board with recommended filler paper tapes, finisher and two coats of primer suitable for gypsum board as per manufactures specifications and also including the cost of making openings for light fittings, grills, diffusers, cutouts made with frame of perimeter channels suitably fixed all complete as per drawing and specifications and direction of the Engineer-in-charge but the excluding the cost of painting.	46.00	Sqm.	824.00	37904.00
Total						176362.00


Junior Engineer
J.D.A., Jodhpur


Assistant Engineer
J.D.A., Jodhpur

Rs. 1.76 Lacs

Executive Engineer
J.D.A., Jodhpur