

जोधपुर नगर निगम, (दक्षिण)

पोलोटैक्निक कॉलेज परिसर, रेजीडेन्सी रोड, जोधपुर

E-Mail-nnjelectrical@gmail.com

क्रमांक :- एफ.14/रो./कार्य/2023/RL-13341

दिनांक :- 23/05/2023

निविदा सूचना

U.B. No. DLB2324GSOB07581

जोधपुर नगर निगम में पंजीकृत संवेदक/अन्य विभागों में पंजीकृत संवेदक/निर्माता/अधिकृत विक्रेता से सिलबन्ध निविदाये आमंत्रित की जाती हैं।

क्र.सं	कार्य का नाम	अनु.लागत लाखों में	धरोहर राशि रूपये	निविदा प्रपत्र मूल्य	कार्य करने की अवधि
01	नगर निगम मुख्यालय में निम्न कक्षाओं में A.C. लगाने का कार्य।	3.75	7500/-	200/-	

निविदा बेचने की दिनांक/समय	दिनांक 6/06/23 समय : 12.00 PM
निविदा प्राप्त करने की दिनांक/समय	दिनांक 6/06/23 समय : 2.00 PM
निविदा खोलने की दिनांक/समय	दिनांक 6/06/23 समय : 2.30 PM

यह निविदा वेबसाइट www.sppp.raj.nic.in एवं <https://urban.rajasthan.gov.in/MCJS> पर देखी जा सकती हैं।

निविदा की महत्वपूर्ण शर्तें निम्नानुसार हैं:-

- अमानत राशि/धरोहर राशि निविदा प्रपत्र में दर्शाई गई कुल अनुमानित लागत की दो प्रतिशत होगी एवं जोधपुर नगर निगम में पंजीकृत संवेदकों से 1/2% धरोहर राशि पी डब्ल्यू एफ एण्ड एआर के नियमानुसार देय होगी। इसके अतिरिक्त सभी संवेदकों से 2% अमानत राशि देय होगी।
- वित्त विभाग (जी एण्ड टी) राजस्थान नोटिफिकेशन दिनांक 22.10.2021 के अनुसार लोक उपापन में पारदर्शिता नियम 2013 के नियम 75 ए अनुसार अतिरिक्त परफोरमेंस सिक्योरिटी जमा करानी होगी।
- संवेदक नगर निगम जोधपुर एवं अन्य राजकीय विभाग में जहाँ पर पंजीकृत, निर्माता, अधिकृत विक्रेता का हो उसका प्रमाण-पत्र संलग्न करना होगा, अन्यथा निविदा पर विचार नहीं किया जाएगा।
- यदि किसी कारणवश उस दिन अवकाश रहता है, तो अगले दिन उसी समय व उसी स्थान पर निविदाये खोली जायेगी।
- निविदा खोलने की दिनांक से 60 दिवस तक निविदा स्वीकृति हेतु मान्य रहेगी। यदि निविदाकर्ता उस अवधि में अपनी निविदा अथवा शर्तों में किसी प्रकार का संसोधन करता है अथवा अपनी निविदा वापस ले लेता है तो उसकी धरोहर राशि जब्त कर ली जायेगी।
- यदि संवेदक का नजदीकी रिश्तेदार (प्रथम रक्त सम्बन्धी व उनके पति/पत्नि) इस कार्य से सम्बन्धित जोधपुर नगर निगम कार्यालय में कार्यरत लेखाकार अथवा तकनीकी स्तर का किसी पद पर पदस्थापित हो तो इस कार्य पर नियुक्त करने पर प्रतिबन्ध रहेगा।
- राज्य सरकार में किसी भी अभियांत्रिकी विभाग में किसी भी इंजीनियर अथवा इंजीनियरिंग या प्रशासनिक कार्य पर नियुक्त राजपत्रित अधिकारी, राज्य सरकार की अनुमति के बिना सेवा निवृत्ति के 2 वर्ष तक संवेदक अथवा उसके कर्मचारी के रूप में कार्य नहीं कर सकेगा।
- किसी निविदा को स्वीकार करने एवं बिना कारण बताये निरस्त करने के समस्त अधिकार सक्षम अधिकारी के पास सुरक्षित है। आर.पी.डब्ल्यू.ए-100की समस्त शर्तें मान्य होगी।
- संवेदक को निविदा के साथ जीएसटी रजिस्ट्रेशन लगाना आवश्यक होगा अन्यथा निविदा पर विचार नहीं किया जाएगा।

(अनुमोदित प्रकाश)
L.A.S
आयुक्त

नगर निगम, (दक्षिण), जोधपुर

दिनांक :- 23/05/2023

क्रमांक :- एफ.14/रो./कार्य/2023/RL-13342 to 13345

प्रतिलिपि :-

- सम्पादक राजस्थान संवाद जयपुर आगामी अंक में एक राज्य स्तरीय संस्करण में प्रकाशित कर बिल भुगतान हेतु प्रस्तुत करें।
- लेखाधीकारी, नगर निगम (दक्षिण), जोधपुर।
- बिल लिपिक, नगर निगम, (दक्षिण), जोधपुर।
- नोटिस बोर्ड, नगर निगम, (दक्षिण), जोधपुर।

आयुक्त
नगर निगम, (दक्षिण), जोधपुर।

JODHPUR MUNICIPAL CORPORATION (SOUTH), JODHPUR


Work: Supply and fixing of AC in various rooms in Nagar Nigam South Office

RUIDP-2022

Schedule

S.No.	Code	Item	Qty	Unit	Rate	Amount
1	E221900	Supply , Installation, Testing and Comissioning of ISO certified company made Air Cooled Hi Wall split type Air conditioners with latest star rating system as per BEE amended upto date complete with Indoor unit(IDU), Out door unit (ODU), surface / concealed copper Refrigerant piping with insulation (closed cell elastomeric nitrile rubber tubular pipe section) upto 3 Mtr (IDU to ODU), copper power cable upto 3.5 Mtr (IDU to ODU), R-32/R-410/ R-407 Green Refrigerant, wireless Remote control, suitable for working between 180-260V with low & high voltage cutoff and 50 hz ,1 phase AC supply capable of performing cooling, dehumidification, air circulation of following capacity with Scroll / rotary compressor. Min 5 year OEM warranty both compressor and PCB. NABL accredateed as per IS/ISO/IEC 17025 standards / CPRI/ ERDA lab testing reports as per IS 1391(Part-2) 2018 with OEM certificate must submitted to engineer in charge. All as per pre approved by Engineer in charge. All as per pre approved by Engineer in charge. For additional technical parameters of products/ work , refer Annexure "A" attached with this BSR .				
	E221920	Invertor Type				
	E221925	1.8/2.0 TR with 3 star rating of BEE(ISEER not less then 3.5)	5	Nos	61693.00	308465.00
2	E223200	Supply & fixing MS powder coated stand suitable for 1.0/1.5/ 2.0 Tr outdoor type of Split AC. All as per pre approved by Engineer in charge. For additional technical parameters of products/ work , refer Annexure "A" attached with this BSR .	5	Nos	1055.00	5275.00
3	E222300	Supply , Installation, Testing and Comissioning of Interconnecting refrigerant copper pipe for split of DHE Grade C12200- ASTM B68, B75, chemical composition of copper %- 99.0 Min and Phosphorus %- 0.015 to 0.040 . For Annealed copper tube :- Tensile strength = 210 Mpa wih elongation % = 40 Min . Ink Mark Brand Printing on Hard Tubes should be present. Material Test Certificate required with each supplied material. Piping between each set of indoor & outdoor units of different sizes as per OEM requirement & specifications including chase cutting, supports, making good the same with sand cement plaster etc. as required. All as per pre approved by Engineer in charge. For additional technical parameters of products/ work , refer Annexure "A" attached with this BSR .	40	Kg	1199.00	47960.00
4	E222400	Supply & fixing of external thermal closed cell elastomeric nitrile rubber Insulation material FM/UL approved with high water vapor diffusion resistance and low thermal conductivity should be certified 'Class O' in Fire Propagation as per BS 476 Part 6 in form of tubular insulation between each set of indoor & outdoor units as per specifications nitrile including cost of adhesive complete as per specification and as required. All as per pre approved by Engineer in charge. For additional technical parameters of products/ work , refer Annexure "A" attached with this BSR .				
	E222410	6mm thick insulation	20	Mtrs.	55.00	1100.00
	E222419	6mm thick insulation and 32 mm internal Dia				
5	E222500	Providing & Fixing of ISI marked (IS : 15778 - 2007) Rigid CPVC drain water piping 6 kg/ cm2 with fittings like elbow, soket, Tee etc & support with MS hanger on ceiling or recessed in wall with chasing & plastering with 6 mm thick closed cell elastomeric nitrile rubber insulation complete in all respect. All as per pre approved by Engineer in charge. For additional technical parameters of products/ work , refer Annexure "A" attached with this BSR .	20	Mtrs.	229.00	4580.00
	E222502	25 mm dia				

6	E224000	Dismantling of split air conditioner of any capacity/any type including existing indoor unit & outdoor unit , refrigerant piping , connecting cables , drain pipe etc. including shifting of dismantled material to store complete as required	1	Job	647.00	647.00
7	E222700	Supply & Fixing of FR PVC insulated & sheathed 3 core flexible copper conductor as per PWD specification for electrical Works confirming to IS:694 and as per IS 8130 : 2013 of 1.1 kV grade .Wire should be made from 99.99% purity copper, class 5 stranding in acc. to IEC 60228 for lower watt loss , oxygen free (<10 ppm) for less chances of oxidization and higher silver content for gives better conductivity , insulation PVC type A ,flame retardant as per IS 10810-53, better amperage rating as per VDE 0298 part 4 including making connection etc. as required. OEM Must have its own in house NABL lab setup for all testing facilities for wires. All as per pre approved by Engineer in charge, making connections. For additional technical parameters of products/ work , refer Annexure "A" attached with this BSR .				
	E222703	4.0 Sq.mm	50	Mtrs.	122.00	6100.00
Total (Rs.)						374127.00


XEN(Elect)
JMC

I agree to do above "G" Schedule work Above/ Below RUIDP 2022 and JMC terms and conditions..

Signature of Contractor