



# कार्यालय नगर निगम जोधपुर दक्षिण

पोलोटेक्निक कॉलेज, रेजीडेन्सी रोड, जोधपुर  
ceo\_nnj@rediffmail.com"tel 02912651464 fax 2651466



क्रमांक:-न.नि.जो./दक्षिण/SBM/2022-23/270

दिनांक:-01/02/2023

## अल्पकालीन निविदा सूचना (यूनिक बिड संख्या .....

नगर निगम जोधपुर दक्षिण की ओर से निम्नलिखित कार्यो हेतु भारत सरकार एवं राज्य सरकार के विभिन्न विभागो/स्वायतशाषी/निगमो/बोर्डो/राजकीय उपक्रमों में पंजीकृत ए.0ए व ए. श्रेणी में पंजीकृत तथा नगर निगम जोधपुर में निर्धारित श्रेणी में पंजीकृत नियमानुसार योग्य संवेदको से निर्धारित प्रपत्र में मुहरबन्द निविदा आमत्रित की जाती है। निविदा दिनांक .... 16/02/2023 को 12:30 बजे तक बेची जाकर, दिनांक 16/02/2023 को दोपहर 2:00 बजे तक प्राप्त कर 3:00 बजे उपस्थित संवेदको के समक्ष खोली जायेगी। अन्य विवरण एवं शर्त निविदा प्रपत्र कार्यालय समय में कार्यालय में देखे जा सकते है। है। [www.sppp.rajasthan.gov.in](http://www.sppp.rajasthan.gov.in), एवं जोधपुर नगर निगम, दक्षिण की website <http://urban.rajasthan.gov.in/mcjs> पर देखी जा सकती है।

क्र. सं.	कार्य का नाम	अनु. लागत लाखों में	धरोहर राशि	निविदा शुल्क	कार्य पूर्ण करने की अवधि
1	REPAIRING OF TOILETS & URINALS AT VARIOUS PLACES IN WORD NO. 1 TO 28 IN NAGAR NIGAM JODHPUR SOUTH	4.97	9,940/-	500/-	3 माह
2	REPAIRING OF TOILETS & URINALS AT VARIOUS PLACES IN WORD NO. 29 TO 55 IN NAGAR NIGAM JODHPUR SOUTH	4.97	9,940/-	500/-	3 माह
3	REPAIRING OF TOILETS & URINALS AT VARIOUS PLACES IN WORD NO. 56 TO 80 IN NAGAR NIGAM JODHPUR SOUTH	4.97	9,940/-	500/-	3 माह
4	जोधपुर नगर निगम दक्षिण के विभिन्न स्थानों पर साईन बोर्ड लगाने का कार्य ।	1.81	3620/-	500/-	1 माह

नोट:-(1) दरे तीन माह तक मान्य होगी। (2) कार्य शुरू करने से पूर्व व कार्य पूर्ण करने के पश्चात् कार्य स्थल की फोटो आवश्यक रूप से प्रस्तुत करे। (3) सशर्त निविदा स्वीकार नहीं होगी। (4) दोष निवारण अवधि नियमानुसार होगा। (5) धरोहर राशि के डिमाण्ड ड्राफ्ट की वैधता निविदा की जा सकती है। (6) आयुक्त नगर निगम जोधपुर के आदेश क्रमांक 9836 दिनांक 7.02.2020 एवं 9975 दिनांक 14.07.2020 अनुसार पंजीयन रिव्यू आदेश के तहत निविदा स्वीकार/अस्वीकार की जायेगी। (7) श्रीमान निदेशक, स्वायत शासन विभाग, राजस्थान जयपुर के आदेश क्रमांक 144612-825 दिनांक 22.11.21 की पालना में वित्त विभाग की अधिसूचना आर.टी. पी.पी. नियम 2013 में Additional Performance Security के लिये नियम 75-ए के अनुसार Additional Performance Security जमा करवानी होगी।

अरुण कुमार पुरोहित  
(I.A.S)

आयुक्त  
जोधपुर नगर निगम, दक्षिण  
दिनांक : 01/02/2023

क्रमांक 271 to 274  
प्रतिलिपि :-

1. महापौर महोदया , नगर निगम जोधपुर दक्षिण ।
2. निजी सहायक, आयुक्त महोदय, नगर निगम जोधपुर दक्षिण ।
3. लेखाधिकारी, नगर निगम जोधपुर दक्षिण (संबंधित) ।
4. अधिशाषी अभियंता नगर निगम जोधपुर दक्षिण (संबंधित) ।
5. सहायक अभियंता/ कनिष्ठ अभियंता, नगर निगम जोधपुर दक्षिण (संबंधित) ।
6. श्री रामेश्वर गहलोत, प्रोग्रामर नगर निगम जोधपुर दक्षिण को भेजकर लेख है कि उक्त अल्पकालीन ई-निविदा सूचना (1) [urban.rajasthan.gov.in/mcjs](http://urban.rajasthan.gov.in/mcjs) (2) [sppp.rajasthan.gov.in](http://sppp.rajasthan.gov.in) पर अपलोड करे एवं निविदा सूचना जोधपुर क्षेत्रीय समाचार पत्र में प्रकाशन हेतु राजस्थान संवाद जयपुर को मेल के माध्यम से भिजवाये।
7. सूचना पट्ट नगर निगम जोधपुर, दक्षिण ।

आयुक्त  
जोधपुर नगर निगम, दक्षिण

# OFFICE OF THE NAGAR NIGAM, JODHPUR

Based on RUIDP bsr 2022

## G-SCHEDULE

NIT No. 270      Date 01/02/2023

Sr No. 02

Last Date of Sale :-

Earnest Money : Rs. ....

Date of Receipt :-

CR No. .... Dated. ....

Copy issued to M/s .....

**Name of work:-Repairing of toilets and urinals at various places in ward no. 29 to 55 in nagar nigam jodhpur south**

S.No.	Item	Qty.	Unit	Rate in Rs.	Amount
1	Earth work in excavation in foundation, trenches etc. including dressing of sides and ramming of bottoms, including getting out the excavated material, refilling after laying pipe/ foundation and disposal of surplus excavated material at a lead upto 50m suitable site as per direction of Engineer for following depths, below natural ground / Road top level. In all types soils/ saturated soil such as moorum, sand, sandy silt, clay, black cotton soil, kankar, etc. Depth upto 1.5 m	16.2	cum	210.5	3410.1
2	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering - All work upto plinth level :1:4:8 (1 Cement : 4 fine/ coarse sand : 8 graded stone aggregate 40 mm nominal size).	0.4	cum	4340.00	1736
3	Random rubble masonry with hard stone in foundation and plinth : Cement mortar 1:6 (1 cement : 6 coarse sand)	3.8	cum	4245.00	16131
4	Coursed rubble masonry (second sort) with hard stone in foundation & plinth with :Cement mortar 1:6 (1 cement : 6 coarse sand)	7.6	cum	4930.00	37468
5	Extra for coursed rubble masonry with hard stone (first or second sort) in superstructure above plinth level and upto two stories.	7.6	cum	890.00	6764
6	Half brick masonry with FPS bricks of class designation 75 in superstructure above plinth level upto two stories.Cement mortar 1:4 (1 cement :4 coarse sand)	2.8125	cum	704.00	1980
7	Cement plastering including T&P, scaffolding, material and complete labour, including cost of water, curing, racking of joints etc. with 20 mm cement plaster of mix : 1:4 (1 cement : 4 fine/ coarse sand)	117.5	sqm	284.00	33370
8	P & F Marble Urinal Partition slab both sides polished of approved design cut from marble size 900x600mm. IS 2556 (Part VI Sec.4)- 1995.Makrana 'Adanga' or Raj Nagar 1st Quality White or Andhi Indi-Italian marble.	8	each	764.00	6112
9	Providing and fixing 1st quality standard white, grey, ivory, fume red brown, light green, light blue and other light shades glazed tiles confirming to IS : 13753 & IS :15622 of size 200mm x 300mm in walls, floors, steps, pillars etc. laid on a bed of neat cement slurry finished with flush pointing in the white cement mixed with pigment to match the shade of the tile complete (excluding the cost of cement plaster on walls and pillar).	30	each	837.00	25110

10	Providing and fixing 1st quality MAT finished ceramic tile size 300x300mm conforming to IS : 13755 and IS : 15622 colour such as white, grey, ivory, fume red brown, light green, light blue and other light shades in floors, steps, pillars etc. laid on a bed of neat cement slurry finished with flush pointing in the white cement mixed with pigment to match the shade of the tile complete (including the cost of cement mortar bed 1:4).	15.00	sqm	814.00	12210
11	Providing and fixing white vitreous china pedestal type water closet (European type W.C. pan) with seat and lid, 10 litre low level white P.V.C. flushing cistern with manually controlled device (handle lever), conforming to IS : 7231, with all fittings and fixtures complete including cutting and making good the walls and floors wherever required :W.C. pan with ISI marked white solid plastic seat and lid	10.00	each	4595.00	45950
12	Providing and fixing water closet squatting pan (Indian type W.C. pan ) with 100mm sand cast Iron P or S trap, 10 litre low level white P.V.C. flushing cistern with manually controlled device (handle lever) conforming to IS : 7231, with all fittings and fixtures complete including cutting and making good the walls and floors wherever required : White Vitreous china Orissa pattern W.C. pan of size 580x440mm with integral type foot rests.	10.00	each	4775.00	47750
13	Providing and fixing wash basin with C.I. brackets, 15 mm C.P. brass pillar taps,32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require :White Vitreous China Wash basin size 630x450 mm with a pair of 15 mm C.P. brass pillar taps.	10.00	each	2620.00	26200
14	Carriage of materials by mechanical transport including loading, unloading and stacking : Earth 5 km	15.00	cum	245.95	3689.25
15	Providing and fixing white vitreous china flat back or wall corner type lipped front urinal basin of 430x260x350mm and	10.00	each	4505.00	45050
16	Providing and fixing gun metal non-return valve of approved quality (screwed end) : 25mm nominal bore vertical	5.00	each	705.00	3525
17	Providing and fixing chlorinated polyvinyl chloride (CPVC) pipes, having thermal stability for hot & cold water supply				0
	15mm nominal outer dia. Pipes.	20.00	metre	187.00	3740
	25mm nominal outer dia. Pipes	20.00	metre	308.00	6160
18	Providing and placing on terrace (at all floor levels) polyethylene water storage tank ISI : 12701 marked with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank	10000.00	per litre	8.80	88000
19	Providing and fixing PTMT bib cock of approved quality and colour. 15mm nominal bore, 86 mm long. Weighing not less than 86 gms.	25.00	each	147.00	3675
20	Providing at site, lowering & laying in trenches, aligning & jointing of PVC-U pipes (SN 8) as per IS 15328 (amended up to date) and as per specifications with rubber rings with socket and spigot joint, (EPDM/SBR) for all depths for pipe length as per drawing and specification including hydraulic field testing (including the cost and conveyance of water to site for testing) and commissioning etc complete as directed by Engineer. Note : E/w to be measured and paid separately.				0

	110 mm nominal dia.	30.00	metre	267.50	8025
	160 mm nominal dia.	30.00	metre	558.00	16740
21	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade : Two or more coats on new work.	100.00	sqm	97.50	9750
22	Distemping with oil bound washable distemper of approved brand and manufacture to give an even shade New work (two or more coats) over and including priming coat with cement primer.	100.00	sqm	125.00	12500
23	P & F Inlet Connection (Angle Valves) Superior quality, of approved make, for Wash basin, Gyser etc.C.P. Inlet connection 15mm.Brass (IS : 8931 marked) with 37 cm long pipe and nut.	5.00	each	432.00	2160
24	P & F Flush Cock / Flush Valve (IS : 9758 Mark) or WC of approved quality make :C.P brass Half-turn exposed 25mm nominal bore	5.00	each	547.00	2735
25	Steel work welded in built up sections/ framed work including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required.In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.	50.00	each	548.00	27400
<b>Total</b>					<b>497340.35</b>
<b>Say</b>					<b>4.97 lacs</b>

**Terms and Condition :-**

1. सभी प्रकार के कर (टैक्स) संवेदक द्वारा ही वहन किये जायेंगे।
2. कार्य स्थल पर श्रमिक व सामग्री की सुरक्षा की जिम्मेवारी संवेदक की होगी।
- 3.जी.सारणी में वर्णित कार्यों के अतिरिक्त व अधिक कार्य संवेदक द्वारा दी गई दरों के आधार पर करवाये जा सकेंगे।
- 4.कार्य स्थल पर कार्य सम्बंधित सूचनाएं दर्शाने वाला बोर्ड संवेदक को स्वयं के स्तर पर लगाना होगा।
- 5.टंकण त्रुटी की अवस्था में सम्बन्धित रेट मान्य होगी।
6. कार्य करने से पूर्व एवं कार्य करने के पश्चात कार्य स्थल की फोटो/विडियोग्राफी सीडी आवश्यक रूप से कार्यालय
7. दोष निवारण अवधि नियमानुसार रहेगी।
8. दरें 4 माह तक मान्य रहेगी
- 9 सशर्त निविदा स्वीकार नहीं होगी।



EXECUTIVE ENGINEER

NAGAR NIGAM SOUTH JODHPUR.

I/We hereby agree to do the above work @ \_\_\_\_\_ Above/below the "G" Schedule.

(Signature of Contractor)