

JODHPUR NAGAR NIGAM, SOUTH

RUIDP BSR 2022

G-SCHEDULE

NIT No. _____ Date _____

Last Date of Sale :- _____

Date of Receipt :- _____

Sr No. _____

Earnest Money : Rs. _____

CR No. _____ Dated. _____

Copy issued to M/s _____

| Name of Work - Construction of Indira Rasoi at | | | | | |
|--|---|--------|-------|---------|-----------|
| S.No. | Item | Qty | Unit | Rate | Ammount |
| 1 | Earth work in excavation in foundation, trenches etc. Including dressing of sides and ramming of bottoms, including getting out the excavated material, refilling after laying pipe/ foundation and disposal of surplus excavated material at a lead upto 50m suitable site as per direction of Engineer for following depths, below natural ground / Road top level. In hard rock (Blasting prohibited) Depth upto 1.5 m | 39.89 | cum | 269.00 | 10730.41 |
| 2 | Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering - All work upto plinth level 1:4:8 (1 Cement : 4 fine/ coarse sand : 8 graded stone aggregate 40 mm nominal size). | 7.98 | Cum | 4340.00 | 34633.20 |
| 3 | Random rubble masonry with hard stone in foundation and plinth :Cement mortar 1:6 (1 cement : 6 coarse sand) | 23.64 | Cum | 4245.00 | 100351.80 |
| 4 | Brick work with FPS bricks of class designation 75 in superstructure above plinth level upto two stories in all shapes and sizes in :Cement mortar 1:6 (1 cement : 6 coarse sand) | 21.66 | cum | 5750.00 | 124545.00 |
| 5 | Half brick masonry with FPS bricks of class designation 75 in superstructure above plinth level upto two stories Cement mortar 1:4 (1 cement :4 coarse sand) | 8.25 | Sqm. | 704.00 | 5808.00 |
| 6 | S&F following sizes (dia.) of ISI marked MMS (IS:9537 P - III) vergin material PVC conduit as per PWD specification for electrical Works along with its accessories (IS: 3419) as required in recess including cutting the wall, covering conduit and making good the same as required. All relative and latest acceptance tests reports by any NABL accredited lab for the conduit shall be submitted before execution & All as per pre approved by Engineer in charge. For additional technical parameters of products/ work , refer Annexure "A" attached with this BSR MMS (IS:9537 P - III) PVC conduit 25 mm | 30.00 | rmt | 37.00 | 1110.00 |
| 7 | Cement plastering including T&P, scaffolding, material and complete labpour, including cost of water, curing, racking of joints etc. with 20 mm cement plaster of mix : 1:6 (1 cement : 6 fine/ coarse sand) | 214.80 | Sqm | 264.00 | 56707.20 |
| 8 | Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering - All work upto plinth level 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) | 2.56 | cum | 5360.00 | 13708.20 |
| 9 | Providing and fixing 1mm thick M.S. sheet door with frame of 40x40x6mm angle iron and 3mm M.S. gusset plates at the junctions and corners, all necessary fittings complete, including applying a priming coat of approved steel primer. Using flats 30x6mm for diagonal braces and central cross piece. | 11.88 | Sqm. | 3565.00 | 42352.20 |
| 10 | Providing and fixing GI wire gauge of average width of aperture 1.56mm with wire of 0.45mm to existing steel door, window shutter frames with necessary M.S. strip beading 20x3mm with suitable screw at not exceeding 150mm distance etc. complete | 4.32 | sqm | 595.00 | 2570.40 |
| 11 | Providing & Fixing in position, MS fabrication work using angles, sqr tubes, c channels etc for various partition frame as per Design & Instructions & Complete in all aspects . including all materials labour,finishing etc complete | 300.00 | kg | 88.10 | 26430.00 |
| 12 | Distemping with oil bound washable distemper of approved brand and manufacture to give an even shade New work (two or more coats) over and including priming coat with cement primer. | 102.90 | Sqm | 125.00 | 12862.50 |
| 13 | Finishing walls with water proofing cement paint of required shade :New work (Two or more coats applied @ 3.84 kg/10 sqm). | 117.72 | Sqm | 85.40 | 10053.29 |
| 14 | Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @0.90 ltr/10 sqm over an under coat of primer applied @ 0.80 ltr/ 10 sqm of approved brand or manufacture | 11.88 | Sqm | 115.00 | 1366.20 |
| 15 | Providing, lowering, laying in trenches, aligning, fixing in position and jointing socketed rubber gasket type ISI marked uPVC pipes of Class III (6 Kg/sqcm) suitable for potable water with rubber ring joints (as per IS 4985-2000) of following outer dia with all accessories (excluding specials) complete including all material, labour, hydraulic testing and commissioning as per Technical Specifications and as per direction of Engineer 110 mm dia | 6.0 | metre | 300.50 | 1803.00 |
| 16 | Steel work welded in built up sections/ framed work including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works | 700.0 | Kg | 117.50 | 82250.00 |
| 17 | Providing corrugated asbestos cement 6 mm thick sheet roofing and fixing with GI, J or L-hooks, bolts and nuts 8 mm dia GI plain and bitumen washers complete excluding the cost of purlines, rafters and trusses : Above 600 pitch. | 43.55 | sqm | 311.00 | 13544.05 |

| | | | | | |
|----|---|-------|-----------|---------|----------|
| 18 | Kota stone slab flooring 25mm thick over 20 mm (average) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab including rubbing and polishing complete with base of cement mortar 1 : 4 (1 cement : 4 coarse sand) : Area of each slab 900 to 2000 sqcm | 17.00 | sqm | 1299.00 | 22083.00 |
| 19 | Wiring of light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq. mm FR PVC Insulated unsheathed flexible copper conductor 1.1 kV grade and 1.5 sq. mm FR PVC Insulated unsheathed flexible copper earth conductor 1.1 kV grade (IS:694) of approved make In surface / recessed ISI marked medium duty PVC conduit & its accessories, round tiles, 18 SWG M.S. box with earth terminal, screwless cage connectors for neutral looping In switch board & false ceiling point. 6 A switch, 3.0 mm thick phenolic laminated sheet, zinc plated / brass screws, cup washers, making connections, testing etc. as required. (A) Short point (up to 3 mtr.) | 7.00 | Point | 183.00 | 1281.00 |
| | (b) Medium point (upto 6 mtr.) | 7.00 | Point | 299.00 | 2093.00 |
| | (c) Long point (upto 10 mtr.) | 7.00 | Point | 400.00 | 2800.00 |
| 20 | Wiring of 3 pin 5 amp. light plug point with 1.5 sq. mm FR PVC Insulated unsheathed flexible copper conductor 1.1 kV grade and 1.5 sq. mm FR PVC Insulated unsheathed flexible copper earth conductor 1.1 kV grade (IS:694) of approved make In surface / recessed ISI marked medium duty PVC conduit & its accessories, 18 SWG M.S. box with earth terminal, screwless cage connectors for neutral looping In switch board & false ceiling point, 6 A switch, 6 A socket, 3.0 mm thick phenolic laminated sheet, zinc plated / brass screws, cup washers, making connections, testing etc. as required. On board | 7.00 | Point | 89.00 | 623.00 |
| 21 | P & F double ball bearing capacitor start ceiling fan of approved make complete with regulator and other accessories as required. (for estimation purpose only) 1200 mm sweep | 4.00 | Each | 1481.00 | 5924.00 |
| 22 | P&F 240/415 V MCB of breaking capacity not less than 10 KA (B/ C/ D tripping characteristic) ISI marked IS 8828(1996)]/ conforming to IEC 60898 In existing board/sheets including making connections with lugs, testing etc. as required. Single pole MCB 6 A to 32 A rating | 4.00 | Nos. | 161.00 | 644.00 |
| 23 | P & F strip type fluorescent tube fitting fabricated from (CRCA sheet and finished with powder coating / stove enamelled paint)/(extruded non corrosive UV resist EP channel) complete with accessories like (OCCB, starter, starter seat)/ EB, rotor holder, terminal block duly prewired with copper conductor including making connection, testing etc. as required. (without tube 1 X 36 Watts with EB | 6.00 | Each | 287.00 | 1722.00 |
| 24 | P & F surface/recessed type 10 mm thick Teak wood board duly antitermite treated, varnished and fixed by using gutties/ PVC fasteners of following size as required 250 mm x 300 mm | 5.00 | Each | 36.00 | 180.00 |
| 25 | Providing and placing on terrace (at all floor levels) polyethylene water storage tank ISI : 12701 marked with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank | 1000 | per litre | 8.8 | 8800.00 |
| 26 | Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings. This included jointing of pipes & fittings with one step CPVC solvent cement, trenching, refilling & testing of joints complete as per direction of Engineer in Charge. External work | | | | 0.00 |
| | 15 mm nominal outer dia .Pipes | 20 | metre | 187 | 3740.00 |
| | 25 mm nominal outer dia .Pipes | 20 | metre | 307.5 | 6150.00 |
| 27 | Providing and fixing brass bib cock of approved quality :15 mm nominal bore | 5 | Nos | 311.5 | 1557.50 |
| 28 | Providing and fixing brass stop cock of approved quality 15 mm nominal bore | 2 | Nos | 333 | 666.00 |
| 29 | Constructing masonry Chamber 30x30x50 cm, inside with 75 class designation brick work in cement mortar 1:4 (1 cement : 4 coarse sand) for stop cock, with C. I. surface box 100x100 x75 mm (inside) with hinged cover fixed in cement concrete slab 1:2:4 mix (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) necessary excavation foundation concrete 1:5:10 (1 cement : 5 fine sand:10 graded stone aggregate 40mm nominal size) and inside plastering with cement mortar 1:3 (1 cement : 3 coarse sand) 12mm thick finished with a floating coat of neat cement complete as per standard design :With bricks | 2 | Each | 1237 | 2474.00 |
| 30 | Stone slab roofing on ground floor with fine grained stone slab 90mm average thickness from approved quarry including filling of joints slab in cement sand mortar 1:4 with ceiling pointing in cement sand mortar 1 : 3 complete as per specification for span Above 3.00 metre and up to 3.30 metre | 9.00 | sqm | 1398.00 | 12582.00 |
| 31 | Providing and fixing wash basin with C.I. brackets, 15 mm C.P. brass pillar taps, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require :White Vitreous China Wash basin size 630x450 mm with a pair of 15 mm C.P. brass pillar taps. | 2 | Each | 2620 | 5240.00 |
| 32 | Providing and fixing Stainless Steel A ISI 304 (18/8) kitchen sink as per IS 13983 with C.I. brackets and stainless steel plug 40 mm including painting of fittings and brackets, cutting and making good the walls wherever required :Kitchen sink with drain board 510x1040 mm bowl depth 250mm | 2 | Each | 4920 | 9840.00 |

| | | | | | |
|----|--|---|------|------|-----------|
| 33 | Supply of Horizontal Foot Mounted IE2 type 2 Pole TEFC, S1 duty, IP-55, 415 Volts Squirrel cage Enclosure conforming to protection IP55 suitable for operation on 415 +/- 10%V, 3 Phase 50 HZ +/- 5% AC supply with ambient 50 C class F insulation with temperature rise limited to class B Induction Motors conforming to IS-325 & IS 12615 - 2011 with latest amendments. of the following rating 0.55 KW | 2 | Each | 6950 | 13900.00 |
| | | | | | 643124.95 |

Terms and Condition :-

1. सभी प्रकार के कर (टैक्स) संवेदक द्वारा ही वहन किये जायेंगे।
2. कार्य स्थल पर श्रमिक व सामग्री की सुरक्षा की जिम्मेवारी संवेदक की होगी।
3. जी.साराणी में वर्णित कार्यों के अतिरिक्त व अधिक कार्य संवेदक द्वारा दी गई दरों के आधार पर करवाये जा सकेंगे।
4. कार्य स्थल पर कार्य सम्बन्धित सूचनाएं दर्शाने वाला बोर्ड संवेदक को स्वयं के स्तर पर लगाना होगा।
5. टंकण नुटी की अवस्था में सम्बन्धित रेट मान्य होगी।
6. कार्य करने से पूर्व एवं कार्य करने के पश्चात कार्य स्थल की फोटो/विडियोग्राफी सीडी आवश्यक रूप से कार्यालय में जमा कराने होंगे।
7. दोष नियारण अवधि नियमानुसार रहेगी।
8. दरें 4 माह तक मान्य रहेगी
9. सशर्त नियिदा स्वीकार नहीं होगी।



EXECUTIVE ENGINEER
NAGAR NIGAM SOUTH JODHPUR.

I/We hereby agree to do the above work @ _____ Above/below the "C" Schedule.

(Signature of Contractor)

कार्यालय जोधपुर नगर निगम – दक्षिण

क्रमांक:- /विकास/तृतीय/ दक्षिण/ 2022-23/ 1594

दिनांक:- 13/3/2023

:: ई-निविदा सूचना ::
DLB2223WSOB31838

(यू.बी. संख्या.....)

नगर निगम दक्षिण जोधपुर की ओर से निम्नलिखित कार्यो हेतु भारत सरकार एवं राज्य सरकार के विभिन्न विभागों/स्वायत्तशासी/निगमों/बोर्डों/राजकीय उपक्रमों में पंजीकृत ए.0ए व ए. श्रेणी में पंजीकृत तथा नगर निगम जोधपुर में निर्धारित श्रेणी में पंजीकृत नियमानुसार योग्य संवेदको से निर्धारित प्रपत्र में ई-निविदाएं आमंत्रित की जाती है।

महत्वपूर्ण दिनांकों का विवरण

| विवरण | दिनांक |
|--|-----------------------|
| ऑन लाईन निविदा फार्म जमा कराना प्रारम्भ होने की दिनांक व समय | 21-03-2023 / 12-30 PM |
| ऑन लाईन निविदा फार्म जमा कराने की अन्तिम दिनांक व समय | 28-03-2023 / 11-00 AM |
| ऑन लाईन निविदा खोलने की तारीख | — " — / 3-00 PM |
| निविदा शुल्क/धरोहर राशि की मूल प्रति अधीक्षण अभियन्ता कार्यालय में जमा कराने की दिनांक व समयावधि | — " — / 12-00 PM |

| क्र.स. | कार्य का नाम | अनुमानित लागत (राशि लाखों में) | धरोहर राशि | निविदा शुल्क | कार्य पूर्ण करने की अवधि |
|--------|---|--------------------------------|------------|--------------|--------------------------|
| 1 | Construction of Indra Rasoi no.1122 at Bus Stand Dalle Khan chakki, Pal Road, Jodhpur | 06.43 | 12,860 | 500 | 6 Month |

निविदा की महत्वपूर्ण शर्तें निम्नानुसार है :-

- निविदा प्रपत्रों को वेबसाईट <http://eproc.rajasthan.gov.in> से डाउनलोड किया जा सकता है। इन निविदाओं में भाग लेने वाले संवेदको को निविदा को इलेक्ट्रॉनिक फॉरमेट में वेबसाईट <http://eproc.rajasthan.gov.in> पर जमा करानी होगी।
- निविदा की प्रकिया ऑन लाईन होगी।
- निविदा हेतु पात्र संवेदको की श्रेणी -

| | |
|---------------------|---------------------|
| किसी भी सीमा तक | - एए श्रेणी, संवेदक |
| रुपये 300.00 लाख तक | - ए, श्रेणी संवेदक |
| रुपये 150.00 लाख तक | - बी, श्रेणी संवेदक |
| रुपये 50.00 लाख तक | - सी, श्रेणी संवेदक |
| रुपये 15.00 लाख तक | - डी, श्रेणी संवेदक |

- निविदा खोलने की तिथि को किसी कारणवश यदि सम्पूर्ण निविदायें नहीं खोली जा सकती है, तो उसके अगले कार्य दिवस को शेष निविदायें खोलने का कार्य जारी रखा जावेगा।

निविदा प्रकिया -

| | | |
|--------------------|-----------------------|--------------------|
| कार्य | पोटेशियल असेसमेंट | पोस्ट क्वालीफिकेशन |
| सडक | 150 लाख से 500 लाख तक | 500 लाख से अधिक तक |
| अन्य निर्माण कार्य | 100 लाख से 200 लाख तक | 200 लाख से अधिक तक |

| क्र.सं. | शुल्क वितरण | शुल्क | भुगतान का प्रकार | देय |
|---------|--------------|---------------|-----------------------------|-------------------------------|
| 1 | निविदा शुल्क | उपरोक्तानुसार | डिमाण्ड ड्रॉफ्ट / बैंकर चैक | आयुक्त जोधपुर नगर निगम दक्षिण |
| 2 | धरोहर राशि | उपरोक्तानुसार | डिमाण्ड ड्रॉफ्ट / बैंकर चैक | आयुक्त जोधपुर नगर निगम दक्षिण |

| | | | | |
|---|-----------------------------|---|-------------------------------|------------------|
| 3 | ई-टेण्डरिंग प्रक्रिया शुल्क | 50 लाख तक 500/- 50 लाख से उपर एवं 1 करोड तक 1500/- 1 करोड से उपर एवं 5 करोड तक 2000/- 5 करोड से उपर 2500/- | डिमाण्ड ड्राफ्ट/ बैंकर चैक | MD RISEL, JAIPUR |
|---|-----------------------------|---|-------------------------------|------------------|

5. निविदादाता द्वारा निविदा शुल्क, धरोहर राशि एवं प्रक्रिया शुल्क हेतु निम्नलिखित राशि कि मूल प्रति जोधपुर नगर निगम कार्यालय में नियमानुसार निविदा खोले जाने के समय से पूर्व जमा करवाना आवश्यक है। निम्नलिखित डिमांड/बैंकर चैक शुल्क ऑनलाईन निविदा फार्म जमाने की अन्तिम तिथि से पूर्व का होना आवश्यक है।
6. प्रदत्त दरें निविदा खोलने की दिनांक से 90 दिवसों तक निविदा स्वीकृति हेतु मान्य (Valid) रहेगी। यदि निविदाकर्ता उस अवधि में अपनी निविदा अथवा शर्तों में किसी प्रकार का संशोधन करता है अथवा अपनी निविदा वापस ले लेता है, तो उसकी धरोहर राशि जब्त कर ली जावेगी।
7. यदि संवेदक के नजदीकी रिश्तेदार (प्रथम रक्त सम्बन्धी व उनके पति/पत्नी) कार्य से संबंधित अधीनस्थ कार्यालय में खण्डीय लेखाकार अथवा सहायक अभियन्ता से लेकर अधीक्षण अभियन्ता स्तर का किसी भी स्तर पर पदस्थापित हो, तो उसके कार्य पर नियुक्त करने पर प्रतिबन्ध रहेगा।
8. राज्य सरकार में किसी भी अभियांत्रिकी विभाग में किसी भी इंजीनियर अथवा इंजीनियर या प्रशासनिक कार्य पर नियुक्त राजपत्रित अधिकारी राज्य की अनुमति के बिना सेवा निवृत्ति के 2 वर्ष तक संवेदक अथवा उसके कर्मचारी के रूप में कार्य नहीं कर सकेंगे। यदि संवेदक अथवा उसके कर्मचारियों में कोई ऐसा व्यक्ति जिसने राज्य सरकार की उक्त लिखित अनुमति निविदा जमा कराने से पहले अथवा संवेदक के यहां से सेवारत लेने से पहले अनुमति नहीं ली है, तो अनुबन्ध रद्द किया जा सकेगा।
9. उक्त आईटम की दोष निवारण अवधि 3 वर्ष होगी।
10. निविदा में निविदादाताओं से अंतर राशि परफोरमेन्स सिक्यूरिटी के रूप में प्राप्त करने के पश्चात ही स्वीकृति निविदा का कार्यादेश दिया जायेगा।
11. किसी भी निविदा को स्वीकार करने एवं बिना कारण बताये निरस्त करने के समस्त अधिकार निम्नहस्ताक्षर कर्ता को रहेगा। RPWA 100 की समस्त शर्तें उस सीमा तक मान्य/लागू होगी जिस सीमा तक के राजस्थान लोक उपापन पारदर्शिता अधिनियम 2012 एवं नियम 2013 के विरोध में नहीं हो।
12. वित्त विभाग के आदेश संख्या एफ-(1)एफ.डी./जी.एफ. एण्ड ए.आर./2007 दिनांक 30.09.11 (सर्कुलर नं. 19/2011) के अनुसार 50.00 लाख रुपये तक की राशि के कार्यों के लिए 500/- व 50.00 लाख रुपये से अधिक राशि के कार्यों के लिए 1000/- रुपये की राशि निविदा शुल्क के अतिरिक्त देनी होगी जो डिमाण्ड ड्राफ्ट या बैंकर चैक के रूप में देय होगी। यह डिमाण्ड ड्राफ्ट या बैंकर चैक मैनिजिंग डायरेक्ट, आर.आई.एस. एल. के पक्ष में व जयपुर में भुगतान योग्य होना चाहिए।
13. नेगोशिएशन की आवश्यकता होने पर ई-मेल व पत्र द्वारा डाक से सूचित किया जायेगा।
14. ई-टेण्डरिंग के लिए निविदादाता हेतु निर्देश :-
 - इन निविदाओं में दिलचस्पी लेने वाले निविदा दाता निविदा प्रपत्रों का इन्टरनेट साईट <http://www.eproc.rajasthan.gov.in> से देख/डाउनलोड कर सकते हैं।
 - निविदाओं में भाग लेने वाले निविदादाताओं को इन्टरनेट साईट <http://www.eproc.rajasthan.gov.in> पर रजिस्टर करवाना होगा। ऑन लाईन निविदा में भाग लेने के लिए डिजिटल सर्टिफिकेट है इनफोरमेशन टेक्नोलॉजी एक्ट 2000 के तहत प्राप्त करना होगा जो इलेक्ट्रॉनिक निविदा में साईन करने हेतु काम आयेगा। निविदादाता उपरोक्त डिजिटल सर्टिफिकेट सी.सी.ए. द्वारा स्वीकृत एजेन्सी से प्राप्त कर सकते हैं। जिन निविदादाताओं के पास पूर्व में वैध डिजिटल सर्टिफिकेट है, नया डिजिटल लेने की आवश्यकता नहीं है।

- निविदादाताओ को निविदा प्रपत्र इलेक्ट्रोनिक फॉर्मेट में उपरोक्त वेबसाइट पर डिजिटल साईन के साथ प्रस्तुत करना होगा। जिसके प्रस्ताव अकेले भौतिक फॉर्म में स्वीकार्य नहीं होगा।
 - इलेक्ट्रोनिक निविदा प्रपत्रों को जमा कराने से पूर्व निविदादाता यह सुनिश्चित कर लेवे की निविदा प्रपत्रो से संबंधित सभी आवश्यक दस्तावेजो की स्केन कॉपी निविदा प्रपत्रो के साथ अटैच कर दी गयी है।
 - कोई भी टेण्डर इलेक्ट्रोनिकली जमा कराने से किसी कारण से लेट हो जाता है तो उसका जिम्मेदार विभाग नहीं होगा।
 - टेण्डर के प्रपत्रो में आवश्यक सभी सूचियों को सम्पूर्ण रूप से भरकर ऑन लाईन दर्ज करे।
15. निविदायें राजस्थान लोक उपापन पारदर्शिता अधिनियम 2012 एवं नियम 2013 के अन्तर्गत आमंत्रित की जाती है। उपर अंकित समस्त प्रावधान/बंधन उस सीमा तक ही लागु होंगे जिस सीमा तक दे उस विन्दु में उल्लेखित अधिनियम एवं नियमों के विरुद्ध नहीं हो।
 16. आयुक्त नगर निगम जोधपुर के आदेश क्रमांक 9836 दिनांक 07.02.2020 एवं 9975 दिनांक 14.07.2020 के अनुसार पंजीयन रिव्यू आदेश के तहत निविदा स्वीकार/अस्वीकार की जायेगी।
 17. राजकीय अवकाश की स्थिति में अगले कार्य दिवस की तिथि मानी जायेगी।
 18. श्रीमान् निदेशक, स्वायत्त शासन विभाग राजस्थान जयपुर के आदेश क्रमांक 144612-825 दिनांक 22.11.2021 की पालना में वित्त विभाग की अधिसूचना दिनांक 22.10.2021 अनुसार आर.टी.पी.पी. नियम 2013 में Additional Performance Security के लिए नियम 75 -ए के अनुसार Additional Performance Security जमा करवानी होगी


 आ.कृत
 जोधपुर नगर निगम दक्षिण

जोधपुर नगर निगम, जोधपुर-दक्षिण

क्रमांक:- /विकास/तृतीय/ दक्षिण/2022-23/1594

दिनांक:- 13/3/2023

:: ई-निविदा सूचना ::

DLB2223WSOB31838

(यू.बी. संख्या.....)

नगर निगम दक्षिण जोधपुर की ओर से विकास कार्यों हेतु ऑनलाईन निविदा आमंत्रित की जाती है, कार्यों की विस्तृत जानकारी एवं शर्तों इत्यादि वेबसाईट <http://eproc.rajasthan.gov.in>, sppp.raj.gov.in पर व जोधपुर नगर निगम दक्षिण की वेबसाईट urban.rajasthan.gov.in/mcjs देखी जा सकती है।

(सुश्री वनिता सेठ)

महापौर

जोधपुर नगर निगम-दक्षिण



जोधपुर नगर निगम-दक्षिण

क्रमांक:- 1595 to 1602

दिनांक:- 13/3/2023

प्रतिलिपि :- सूचनार्थ एवं आवश्यक कार्यवाही हेतु।

1. श्रीमान जिला कलेक्टर महोदय, जोधपुर।
2. निदेशक/अधीक्षण अभियन्ता, स्थानीय निकाय विभाग, जयपुर।
3. अधीक्षण अभियन्ता/अधिशाषी अभियन्ता, सा.नि.वि./जोधपुर विकास प्राधिकरण जोधपुर।
4. वरिष्ठ लेखाधिकारी, जोधपुर नगर निगम दक्षिण।
5. राजस्थान संवाद, जयपुर को भेजकर लेख है कि निविदा सूचना एक राज्य स्तरीय एवं एक क्षेत्रीय स्तरीय समाचार पत्र में प्रकाशन हेतु भिजवाये एवं समाचार पत्र के नाम बाबत ई-निविदा मेल नगर निगम जोधपुर दक्षिण को भिजवाये।
6. श्री रामेश्वर गहलोत, प्रोग्रामर नगर निगम जोधपुर दक्षिण को भेजकर लेख है कि ई-निविदा सूचना urban.rajasthan.gov.in/mcjs एवं sppp.rajasthan.gov.in, पर अपलोड करें एवम् निविदा सूचना प्रकाशन हेतु राजस्थान संवाद जयपुर को मेल के माध्यम से भिजवायें।
7. सहायक अभियन्ता को भेजकर लेख है कि कार्यों की जी-सारणी एवं ई-निविदा सूचना <http://eproc.rajasthan.gov.in> पर अपलोड करे।
8. सूचना पट्ट जोधपुर नगर निगम दक्षिण।



जोधपुर नगर निगम -दक्षिण