

27/82

जोधपुर नगर निगम-दक्षिण

क्रमांक:- न.नि.जो.-दक्षिण/चतुर्थ/विकास/2022-23/27/82

दिनांक:- 30/1/23

:: अल्पकालीन ई-निविदा सूचना ::

(UB No. DLB2223WSOB26737)

नगर निगम जोधपुर-दक्षिण की ओर से निम्नलिखित कार्यो हेतु भारत सरकार एवं राज्य सरकार के विभिन्न विभागों/स्वायतशासी/निगमों/बोर्डों/राजकीय उपक्रमों में पंजीकृत ए.0ए व ए. श्रेणी में पंजीकृत तथा नगर निगम जोधपुर में निर्धारित श्रेणी में पंजीकृत नियमानुसार योग्य संवेदको से निर्धारित प्रपत्र में अल्पकालीन ई-निविदाएं आमंत्रित की जाती है।

महत्वपूर्ण दिनांकों का विवरण

विवरण	दिनांक
ऑन लाईन निविदा फार्म जमा कराना प्रारम्भ होने की दिनांक व समय	01-02-2023/12:30 PM
ऑन लाईन निविदा फार्म जमा कराने की अन्तिम दिनांक व समय	07-02-2023/11:00 AM
ऑन लाईन निविदा खोलने की तारीख	07-02-2023/12:00 PM
निविदा शुल्क/धरोहर राशि की मूल प्रति अभियन्ता शाखा कार्यालय में जमा कराने की दिनांक व समयावधि	07-02-2023/12:00 PM

निविदा का विवरण निम्न प्रकार है :-

क्र.सं.	कार्य का नाम	कार्य की अनुमानित लागत (लाखों में)	धरोहर राशि	निविदा शुल्क	कार्य पूर्ण करने की अवधि
1	वार्ड संख्या 6 से 21 में नाला मरम्मत कार्य (वार्षिक अनुबंध)	40.00	80000/-	500/-	12 Month
2	वार्ड 6 से 21 में विभिन्न पार्कों में नवीनीकरण व मरम्मत कार्य (वार्षिक अनुबंध)	40.00	80000/-	500/-	12 Month
3	भैरव नाले का मलबा हटाने का एवं फ्लोरिंग का कार्य	21.00	42000/-	500/-	3 Month
4	वार्ड 7 में नाला कवरिंग व पुलिया मरम्मत कार्य	22.00	44000/-	500/-	3 Month
5	नगर निगम जोधपुर दक्षिण के क्षेत्राधिकार में विभिन्न स्थानों पर मरम्मत, चित्रकारी व माण्डने का कार्य	10.00	20000/-	500/-	2 Month

निविदा की महत्वपूर्ण शर्तें निम्नानुसार है :-

- ई-निविदा प्रपत्रों को वेबसाईट <http://eproc.rajasthan.gov.in> से डाउनलोड किया जा सकता है। इन ई-निविदाओं में भाग लेने वाले संवेदको को निविदा को इलेक्ट्रॉनिक फॉरमेट में वेबसाईट <http://eproc.rajasthan.gov.in> पर जमा करानी होगी।
- ई-निविदा की प्रकिया ऑन लाईन होगी।
- नगर निगम जोधपुर में पंजीकृत अथवा अन्य विभाग में पंजीकृत संवेदकों को भी अपने पंजीयन दस्तावेजों को संबंधित पंजीयन अधिकारी से रिव्यू करवा कर प्रस्तुत करना होगा। पंजीयन अथवा रिव्यू दस्तावेज निविदा जमा कराने की अंतिम तिथि पर दो वर्ष से अधिक पुराना होने पर मान्य पंजीयन के अभाव में निविदा निरस्त कर दी जाएगी।
- ई-निविदा हेतु पात्र संवेदको की श्रेणी -
 किसी भी सीमा तक
 रुपये 300.00 लाख तक - एए श्रेणी, संवेदक
 रुपये 150.00 लाख तक - ए, श्रेणी संवेदक
 रुपये 50.00 लाख तक - बी, श्रेणी संवेदक
 रुपये 15.00 लाख तक - सी, श्रेणी संवेदक
 - डी, श्रेणी संवेदक
- ई-निविदा खोलने की तिथि को किसी कारणवश यदि सम्पूर्ण निविदायें नहीं खोली जा सकती है, तो उसके अगले कार्य दिवस को शेष निविदायें खोलने का कार्य जारी रखा जावेगा।
- ई-निविदा प्रकिया -
 कार्य
 सडक
 अन्य निर्माण कार्य
 पोटेथियल असेसमेंट
 100 लाख से 500 लाख तक
 100 लाख से 200 लाख तक
 पोस्ट क्वालीफिकेशन
 500 लाख से 2000 लाख तक
 200 लाख से 1000 लाख तक
- निविदादाता द्वारा निविदा शुल्क, धरोहर राशि एवं प्रकिया शुल्क हेतु निम्नलिखित राशि कि मूल प्रति जोधपुर नगर निगम कार्यालय में नियमानुसार निविदा खोले जाने के समय से पूर्व जमा करवाना आवश्यक

है। निम्नांकित कम सं. 3 के कॉलम सं. 5 में अंकित अनुसार किसी प्रकार की त्रुटी पाये जाने पर संवेदक की निविदा कॉपी निरस्त कर दी जायेगी।

क्र.सं.	शुल्क वितरण	शुल्क	भुगतान का प्रकार	देय
1	2	3	4	5
1	निविदा शुल्क	500/-	डिमाण्ड ड्रॉफ्ट / बैंकर चैक	आयुक्त जोधपुर नगर निगम-दक्षिण
2	धरोहर राशि	उपरोक्तानुसार	डिमाण्ड ड्रॉफ्ट / बैंकर चैक	आयुक्त जोधपुर नगर निगम-दक्षिण
3	ई-टेण्डरिंग प्रक्रिया शुल्क	50 लाख एवं उपर 1000/- 50 लाख से नीचे 500/-	डिमाण्ड ड्रॉफ्ट / बैंकर चैक	MD RISL, JAIPUR


नोट :- धरोहर राशि के रूप में कार्य की लागत की 2 प्रतिशत राशि जमा करवानी होगी, नियमानुसार निर्धारित श्रेणी में पंजीकृत संवेदकों को 0.5 प्रतिशत तक धरोहर राशि जमा करवाने के लिए छूट प्रदान की जाएगी।

- 8 प्रदत्त दरें निविदा खोलने की दिनांक से 90 दिवसों तक निविदा स्वीकृति हेतु मान्य (Valid) रहेगी। यदि निविदाकर्ता उस अवधि में अपनी निविदा अथवा शर्तों में किसी प्रकार का संशोधन करता है अथवा अपनी निविदा वापस ले लेता है, तो उसकी धरोहर राशि जब्त कर ली जावेगी।
- 9 यदि संवेदक के नजदीकी रिश्तेदार (प्रथम रक्त सम्बन्धी व उनके पति/पत्नी) कार्य से संबंधित अधीनस्थ कार्यालय में खण्डीय लेखाकार अथवा सहायक अभियन्ता से लेकर अधीक्षण अभियन्ता स्तर का किसी भी स्तर पर पदस्थापित हो, तो उसके कार्य पर नियुक्त करने पर प्रतिबन्ध रहेगा।
- 10 राज्य सरकार में किसी भी अभियांत्रिकी विभाग में किसी भी इंजीनियर अथवा इंजीनियर या प्रशासनिक कार्य पर नियुक्त राजपत्रित अधिकारी राज्य की अनुमति के बिना सेवा निवृत्ति के 2 वर्ष तक संवेदक अथवा उसके कर्मचारी के रूप में कार्य नहीं कर सकेंगे। यदि संवेदक अथवा उसके कर्मचारियों में कोई ऐसा व्यक्ति जिसने राज्य सरकार की उक्त लिखित अनुमति निविदा जमा कराने से पहले अथवा संवेदक के यहां से सेवायें लेने से पहले अनुमति नहीं ली है, तो अनुबन्ध रद्द किया जा सकेगा।
- 11 किसी भी निविदा को स्वीकार करने एवं बिना कारण बताये निरस्त करने के समस्त अधिकार निम्नहस्ताक्षर कर्ता को रहेगा। RPWA 100 की समस्त शर्तें उस सीमा तक मान्य/लागु होगी जिस सीमा तक के राजस्थान लोक उपापन पारदर्शिता अधिनियम 2012 एवं नियम 2013 के विरोध में नहीं हो।
- 12 उक्त आईटम की दोष निवारण अवधि राज्य सरकार द्वारा निर्धारित नोर्म्स के अनुसार होगी। निविदादाता को निविदा भरते समय साथ में निविदा शुल्क, धरोहर राशि, ई-टेण्डरिंग शुल्क Registration की प्रति को स्कैन कर लगाना अनिवार्य है।
- 13 वित्त विभाग के आदेश संख्या एफ-(1)एफ.डी./जी.एफ. एण्ड ए.आर./2007 दिनांक 30.09.11 (सर्कुलर नं. 19/2011) के अनुसार 50.00 लाख रुपये तक की राशि के कार्यों के लिए 500/- व 50.00 लाख रुपये से अधिक राशि के कार्यों के लिए 1000/- रुपये की राशि निविदा शुल्क के अतिरिक्त देनी होगी जो डिमाण्ड ड्राफ्ट या बैंकर चैक के रूप में देय होगी। यह डिमाण्ड ड्राफ्ट या बैंकर चैक मैनजिंग डायरेक्ट, आर.आई.एस.एल. के पक्ष में व जयपुर में भुगतान योग्य होना चाहिए।
- 14 नेगोशिएशन की आवश्यकता होने पर ई-मेल व पत्र द्वारा डाक से सूचित किया जायेगा।
- 15 निविदा शुल्क निम्नानुसार निर्धारित है -

50 लाख से कम अनुमानित लागत	- रुपये 500/-
50 लाख से 150 लाख तक अनुमानित लागत	- रुपये 1000/-
150 लाख से 400 लाख तक अनुमानित लागत	- रुपये 2000/-
400 लाख से अधिक अनुमानित लागत	- रुपये 5000/-
- 16 ई-टेण्डरिंग के लिए निविदादाता हेतु निर्देश :-
 - इन निविदाओं में दिलचस्पी लेने वाले निविदा दाता निविदा प्रपत्रों का इन्टरनेट साईट <http://www.eproc.rajasthan.gov.in> से देख/डाउनलोड कर सकते हैं।
 - निविदाओं में भाग लेने वाले निविदादाताओं को इन्टरनेट साईट <http://www.eproc.rajasthan.gov.in> पर रजिस्टर करवाना होगा। ऑन लाईन निविदा

में भाग लेने के लिए डिजिटल सर्टिफिकेट है इनफोरमेशन टेक्नोलॉजी एक्ट 2000 के तहत प्राप्त करना होगा जो इलेक्ट्रॉनिक निविदा में साईन करने हेतु काम आयेगा। निविदादाता उपरोक्त डिजिटल सर्टिफिकेट सी.सी.ए. द्वारा स्वीकृत एजेन्सी से प्राप्त कर सकते हैं। जिन निविदादाताओं के पास पूर्व में वैध डिजिटल सर्टिफिकेट है, नया डिजिटल लेने की आवश्यकता नहीं है।

- निविदादाताओं को निविदा प्रपत्र इलेक्ट्रॉनिक फॉर्मेट में उपरोक्त वेबसाइट पर डिजिटल साईन के साथ प्रस्तुत करना होगा। जिसके प्रस्ताव अकेले भौतिक फॉर्म में स्वीकार्य नहीं होगा।
 - इलेक्ट्रॉनिक निविदा प्रपत्रों को जमा कराने से पूर्व निविदादाता यह सुनिश्चित कर लेवे की निविदा प्रपत्रों से संबंधित सभी आवश्यक दस्तावेजों की स्कैन कॉपी निविदा प्रपत्रों के साथ अटैच कर दी गयी है।
 - कोई भी टेण्डर इलेक्ट्रॉनिकली जमा कराने से किसी कारण से लेट हो जाता है तो उसका जिम्मेदार विभाग नहीं होगा।
 - टेण्डर के प्रपत्रों में आवश्यक सभी सूचियों को सम्पूर्ण रूप से भरकर ऑन लाईन दर्ज करे।
- 17 निविदायें राजस्थान लोक उपापन पारदर्शिता अधिनियम 2012 एवं नियम 2013 के अन्तर्गत आमंत्रित की जाती हैं। उपर अंकित समस्त प्रावधान/बंधन उस सीमा तक ही लागू होंगे जिस सीमा तक दे उस बिन्दु में उल्लेखित अधिनियम एवं नियमों के विरुद्ध नहीं हो।
- 18 संवेदक द्वारा प्रस्तुत की गयी दरें एक वर्ष तक मान्य होगी।
- 19 राजकीय अवकाश भी स्थिति में आगामी कार्य दिवस की तिथि मान्य होगी।
- 20 श्रीमान निदेशक, स्वायत्त शासन विभाग, राजस्थान जयपुर के आदेश क्रमांक 144612-825 दिनांक 22.11.021 की पालना में वित्त विभाग की अधिसूचना आर.टी.पी.पी. नियम 2013 में Additional Performance Security के लिये नियम 75-ए के अनुसार Additional Performance Security जमा करवानी होगी


(अरुण कुमार पुरोहित)
I.A.S.

आयुक्त
नगर निगम जोधपुर-दक्षिण

27/82

नगर निगम जोधपुर-दक्षिण

क्रमांक:- न.नि.जो.-दक्षिण/चतुर्थ/विकास/2022-23/

दिनांक:- 30/1/23

:: अल्पकालीन ई-निविदा सूचना ::
(UB No. DLB2223WSOB26737.....)

नगर निगम जोधपुर-दक्षिण की ओर से विभिन्न सिविल कार्यों हेतु ऑनलाईन अल्पकालीन ई-निविदाएं आमंत्रित की जाती है। ई-निविदा से संबंधित कार्यों की विस्तृत जानकारी, निविदा की शर्तें आदि <http://eproc.rajasthan.gov.in>, www.sppp.rajasthan.gov.in एवं www.urban.rajasthan.gov.in/mcjs पर देखी जा सकती है।

(वनिता सेठ)
महापौर

नगर निगम जोधपुर-दक्षिण

27/83 to 27/89

क्रमांक:- न.नि.जो.-दक्षिण/चतुर्थ/विकास/2022-23/

प्रतिलिपी :- सूचनार्थ एवं आवश्यक कार्यवाही हेतु।

1. श्रीमान जिला कलेक्टर महोदय, जोधपुर।

2. निदेशक/अधीक्षण अभियन्ता, स्थानीय निकाय विभाग, जयपुर।

3. अधीक्षण अभियन्ता/अधिशाषी अभियन्ता, सा.नि.वि./जोधपुर विकास प्राधिकरण/नगर निगम जोधपुर।

4. वरिष्ठ लेखाधिकारी, जोधपुर नगर निगम।

5. राजस्थान संवाद, जयपुर को भेजकर लेख है कि उक्त अल्पकालीन ई-निविदा नियमानुसार एक राज्य स्तरीय व क्षेत्रीय समाचार पत्रों में प्रकाशन हेतु भिजवाये व jodhpurmcsamvad@yahoo.com पर Intimation Mail की कॉपी भिजवाये।6. श्री रामेश्वर गहलोत, प्रोग्रामर नगर निगम जोधपुर दक्षिण को भेजकर लेख है कि एवं अल्पकालीन ई-निविदा सूचना (1) urban.rajasthan.gov.in/mcjs (2) sppp.rajasthan.gov.in पर अपलोड करें।7. संबंधित सहायक अभियन्ता को भेजकर लेख है कि उपरोक्त अल्पकालीन ई-निविदा के कार्यों की जी-सारणी एवं ई-निविदा सूचना <http://eproc.rajasthan.gov.in> पर अपलोड करावे।

8. सूचना पट्ट जोधपुर नगर निगम।

(अरुण कुमार पुरोहित)
I.A.S.

आयुक्त

नगर निगम जोधपुर-दक्षिण

दिनांक:- 30/1/23

(अरुण कुमार पुरोहित)
I.A.S.

आयुक्त

नगर निगम जोधपुर-दक्षिण

OFFICE OF THE NAGAR NIGAM, JODHPUR
G-SCHEDULE

NIT No. date

Sr No.

Last Date of Sale :-

Earnest Money : Rs.

Date of Receipt :-

CR No. Dated.

Copy issued to M/s

Name of work- Cleaning and nallah flooring work of bhairav nallah on aiims road .


BASED ON RUIDP 2022

S.No.	Item	NO	L	B	H	QTY	Unit	Rate	Amount
1	Sludge clearance of drains, channels and canals with lift 1.5 Mtr and lead up to 50 Mtr.		80	12	0.6	576	cum	372.5	214560
2	Earth work in excavation in foundation, trenches etc. including dressing of sides and ramming of bottoms, including getting out the excavated material, refilling after laying pipe/ foundation and disposal of surplus excavated material at a lead upto 50m suitable site as per direction of Engineer for following depths, below natural ground / Road top level.								
3	In all types soils/ saturated soil such as moorum, sand, sandy silt, clay, black cotton soil, kankar, etc.		80	12	0.6	576	cum	210.5	121248
4	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering - All work upto plinth level ::4:8 (1 Cement : 4 fine/ coarse sand : 8 graded stone aggregate 40mm nominal size).	1	80	12	0.2	192	Cum.	4340	833280
5	Pointing on stone work with cement mortar 1:3 (1 cement : 3 fine sand) :								
6	Flush/ Ruled pointing		20	1.5		30	sqm.	205	6150
7	Providing and laying un-reinforced, dowel jointed, plain cement concrete mix With Concrete Mixer & vibrator pavement over a prepared sub base with 43 grade cement , coarse and fine aggregate conforming to IS: 383, maximum size of coarse aggregate not exceeding 25 mm, mixed as per approved mix design, laid, spread, mpacted and finished in a continuous operation including provision of contraction, xpansion, construction and longitudinal joints, joint filler, separation membrane, sealant primer, joint sealant, debonding strip, admixtures (if required) as approved, curing compound, finishing to lines and grades complete as per drawing and as per clause 602, 112 of MoRT&H specification including all material, labour, machinery, lighting, guarding and maintenance of diversion.PCC M-20	1	80	12	0.15	144	Cum.	5550	799200

8	Carriage of Materials by mechanical transport including loading, unloading and stacking ::10km					1152	Cum.	245.95	283334
9	Dismantling of existing structures like culverts, bridges, retaining walls, CC road and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts and lead of 50 metres as directed by Engineer.	4	1.5	2	2	24	Cum.	620	14880
									2043212

Terms and Condition :-

1. सभी प्रकार के कर (टैक्स) संवेदक द्वारा ही वहन किये जायेंगे।
2. कार्य स्थल पर श्रमिक व सामग्री की सुरक्षा की जिम्मेवारी संवेदक की होगी।
3. जी.सारणी में वर्णित कार्यों के अतिरिक्त व अधिक कार्य संवेदक द्वारा दी गई दरों के
4. कार्य स्थल पर कार्य सम्बंधित सूचनाएं दर्शाने वाला बोर्ड संवेदक को स्वयं के स्तर पर
5. टंकण त्रुटी की अवस्था में सम्बन्धित रेट मान्य होगी।
6. कार्य करने से पूर्व एवं कार्य करने के पश्चात कार्य स्थल की फोटो/विडियोग्राफी सीडी
7. दोष निवारण अवधि नियमानुसार रहेगी।
8. सशर्त निविदा स्वीकार नहीं होगी।
9. निष्पादन सुरक्षा राशि 10 प्रतिशत मय अनुबन्ध के जमा कराना होगा।


EXECUTIVE ENGINEER
NAGAR NIGAM, JODHPUR.

I/We hereby agree to do the above work @ _____ Above/below the "G" Schedule

(Signature of Contractor)

JODHPUR NAGAR NIGAM JODHPUR

G-SCHEDULE

NIT No. date

Least Date of Sale :-

Date of Receipt :-

Copy issued to M/s

Name of work : शर्त 6 से 21 में गीला मरदाना काढ (गोखिप शर्तुकर)

Sr No.
Earnest Money : Rs.
CR No., Dated.

		BSR : PWD BUILDING BSR 2019 & RUIDP BSR 2022					
S.No	Item No.	Particulars	Qty.	Unit	Rate	Amount	
1	R-17.1.1	Earth work for Sewer line and Manhole in excavation in foundation, trenches manholes, road side chambers etc. including dressing of sides and ramming of bottoms, including getting out the excavated material, refilling after laying pipe/ foundation and disposal of surplus excavated material at a lead upto 50m suitable site as per direction of Engineer for following depths, below natural ground / Road top level including allowances for any additional excavation beyond the drawings (measurement for payment to be as per standard drawings), re-handling of material/earth to complete the task. In all types soils/saturated soil such as moorum, sand, sandy silt, clay, black cotton soil, kankar, etc.	1.00	Cum	274.50	274.50	
	17.1.1.1		Add extra for over all depth of excavation above 1.5 m and upto 3.0 m over item no 17.1.1.1	1.00	Cum	19.20	19.20
	17.1.1.3		Add extra for over all depth of excavation above 3.0 m and upto 4.5 m over item no 17.1.1.1	1.00	Cum	43.90	43.90
	17.1.1.4		Add extra for over all depth of excavation above 4.5 m and upto 6.0 m over item no 17.1.1.1	1.00	Cum	76.90	76.90
	17.1.1.5		Add extra for over all depth of excavation above 6.0 m and upto 7.5 m over item no 17.1.1.1	1.00	Cum	118.00	118.00
2	17.1.2.1	Earth work for Sewer line and Manhole in excavation in foundation, trenches manholes, road side chambers etc. including dressing of sides and ramming of bottoms, including getting out the excavated material, refilling after laying pipe/ foundation and disposal of surplus excavated material at a lead upto 50m suitable site as per direction of Engineer for following depths, below natural ground / Road top level including allowances for any additional excavation beyond the drawings (measurement for payment to be as per standard drawings), re-handling of material/earth to complete the task. In ordinary rock. Depth upto 1.5 m					
	17.1.2.2	Add extra for over all depth of excavation above 1.5 m and upto 3.0 m over item no 17.1.2.1	1.00	Cum	1172.00	1172.00	
3	17.1.2.3	Add extra for over all depth of excavation above 3.0 m and upto 4.5 m over item no 17.1.2.1	1.00	Cum	82.00	82.00	
	R-17.3.1	Providing and fixing CLOSE timbering in trenches of sewer line and manholes including strutting, shoring and packing cavities (wherever required) complete. (Measurements to be taken of the face area timbered) for following depth below NGL. Depth upto 3.0 m	1.00	Cum	187.50	187.50	
4	R-17.8	Dismantling of flexible pavements for sewer line and manholes and disposal of dismantled materials up to a lead of 50 metres as directed by Engineer including allowances for any additional dismantling beyond the drawings (measurement for payment to be as per standard drawings), re-handling of material/earth to complete the task	1.00	Sqm	136.00	136.00	
17.8.1	Bituminous courses		1.00	Cum	493.50	493.50	
17.8.2	Granular courses		1.00	Cum	343.50	343.50	

Item No.	Particulars	Qty.	Unit	Rate	Amount
R-17.9	Dismantling of cement concrete pavement for sewer line and manholes by mechanical means using pneumatic tools, cutting the peripheral edge by CC cutter, breaking to pieces not exceeding 0.02 cum in volume and stock piling at designated locations and disposal of dismantled materials up to a lead of 1000 metres including allowances for any additional dismantling beyond the drawings (measurement for payment to be as per standard drawings), rehandling of material/earth to complete the task.	1.00	Cum	1170.00	1170.00
6	B-1.20.2 Pumping out water caused by springs, tidal or river seepage, broken water main or drains and the like with pumping set of following H.P. including P.O.L./Power consumption etc. complete. 10 to 19 H.P.	1.00	Hrs	214.00	214.00
7	R-4.25 Providing Barricading for Trenches using-80 - 100 mm dia Wooden Ballies as vertical post, atleast 1.5m above ground level and atleast 30 45 cm below ground level at a spacing of 3 m. Two rows of PVC Tape (preferably red in colour) strip barricading horizontal strip securely tied by the vertical members. Vertical members shall be painted in red and white colour. Rate is inclusive removal and cleaning of site complete in all respect	1.00	Mtr	104.50	104.50
8	R-17.18. Providing at site, lowering & laying in trenches, aligning & jointing of RCC pipes NP4 class (with s/s ends) IS: 458 - 2003 (amended up to date) marked and pipes from 300 mm and upto 1800 mm manufactured through vertical / vibrated casing process at all depths with Rubber gaskets (EPDM/SBR) for sewer lines as per IS: 5382 (including cost of Rubber gaskets, lubricants) as per drawing, sectional hydro testing of the sewer pipe line (including cost and conveyance of water to site for testing) etc. complete as per specification and / or as directed by Engineer. Note : E/w to be measured and paid separately. Length of pipe shall be measured in between the outer wall of two manholes / inspection chambers. Pipe in the manhole/inspection chamber's wall shall deemed to be included in the item of manhole/inspection chamber shall not be payable.	1.00	Mtr	6070.00	6070.00
		1.00	Mtr	3790.00	3790.00
		1.00	Mtr	2715.00	2715.00
		1.00	Mtr	1158.00	1158.00
9	R-17.30 Providing granular bedding having width = outer dia of pipe (Bc) + 500mm, thickness below pipe = 0.25Bc or 100mm (whichever is higher) and haunching = 0.5Bc, with graded hard crusher broken stone of 100% passing through 20mm sieve, 20 to 50 % passing through 10mm sieve and 100 % retain on 6.3mm sieve, laying in layers of thickness 10/15cm including ramming, consolidation etc complete for all type of pipes of following sizes as per drawing and or as directed by Engineer. a) 800 mm internal diameter b) 600 mm internal diameter c) 450 mm internal diameter d) 300 mm internal diameter	1.00	Mtr	653.00	653.00
		1.00	Mtr	467.50	467.50
		1.00	Mtr	335.50	335.50
		1.00	Mtr	199.50	199.50
10	R-32.3.3 Cement plastering including T&P, scaffolding, material and complete labour, including cost of water, curing, racking of joints etc. with 20 mm cement plaster of mix : 1:6 (1 cement : 6 fine/ coarse sand)	1.00	Sq.m	264.00	264.00
11	B-6.27.1 Supplying and fixing Soorsagar Bhura or Equivalent ashlar sills, lintels and dassa, bearing, bed & top surface made perfectly even, jambs, skirting steps etc. rough dressed : Upto 15 cm. thick	1.00	Cum	4473.00	4473.00
12	R-25.1.1 Random rubble masonry with hard stone in foundation and plinth : Cement mortar 1:6 (1 cement : 6 coarse sand)	1.00	Cum	4245.00	4245.00
13	R-25.1.1 Random rubble masonry with hard stone in foundation and plinth : Cement mortar 1:6 (1 cement : 6 coarse sand) Extra for random rubble masonry with hard stone in superstructure above plinth level and upto two stories.	1.00	Cum	5135.00	5135.00

Item No.	Particulars	Qty.	Unit	Rate	Amount
R-17.80.1	Supplying & fixing 560mm dia SFRC manhole frame & cover as per IS : 12592-2002 in existing manholes including grouting the frame in PCC M-15 complete in all respect as directed by the Engineer. HD-20	1.00 Nos		2685.00	2685.00
R-9.3	Providing and laying lean cement concrete 1:4:8 in Sub- base over a prepared sub-grade with coarse and fine aggregate conforming to IS: 383, the size of coarse aggregate not exceeding 25 mm, aggregate cement ratio not to exceed 15:1, aggregate gradation after blending to be as per table 600-1, cement content not to be less than 150 kg/ cum, optimum moisture content to be determined during trial length construction, concrete strength not to be less than 10 Mpa at 7 days, mixed in concrete mixer, laid manually, compacted with surface vibrator, finishing and curing complete as per clause 601, 112 of MoRT&H specification including all material, labour, machinery, lighting, guarding and maintenance of diversion.	1.00 Cum		2775.00	2775.00
R-9.5.1	Providing and laying un-reinforced, dowel jointed, plain cement concrete mix With Concrete Mixer & vibrator pavement over a prepared sub base with 43 grade cement, coarse and fine aggregate conforming to IS: 383, maximum size of coarse aggregate not exceeding 25 mm, mixed as per approved mix design, laid, spread, compacted and finished in a continuous operation including provision of contraction, expansion, construction and longitudinal joints, joint filler, separation membrane, sealant primer, joint sealant, debonding strip, admixtures (if required) as approved, curing compound, finishing to lines and grades complete as per drawing and as per clause 602, 112 of MoRT&H specification including all material, labour, machinery, lighting, guarding and maintenance of diversion. PCC M-20	1.00 Cum		5550.00	5550.00
17	R-17.85 Emptying of domestic septic tank/ soakage well etc, disposing of sludge within a lead of 5km and taking out sewage by mechanical means including refilling with local earth, ramming and compaction in layers, cleaning of site.	1.00 Nos		4630.00	4630.00
18	R-4.13 Earth filling with available surplus soil excavated from foundations and taken only from outside of building plinth in layers not exceeding 20cm in depth, consolidating each deposited layer including ramming and watering and consolidation with lead up to 50 m and lift upto 1.5 m.	1.00 Cum		144.00	144.00
19	R-11.1 Carriage of Materials by mechanical transport including loading, unloading and stacking : Earth	1.00 Cum		245.95	245.95
20	R-30.35 Random rubble dry stone Kharranja (soiling) under floor.	1.00 Cum		1838.50	1838.50
21	R-17.42 Providing and constructing of RR stone masonry circular manholes of "Type-A" with internal dia 0.90m and depth upto 1.65m having 300mm thick RR stone masonry wall in cement-sand mortar 1:4, including concreting PCC M-10 grade (1:4:8) for 225mm thick foundation including curing compaction and form work etc complete, PCC M15 for benching and channel portion, RCC M20 for fixing the manhole frame and including reinforcement, PCC M20 for fixing the manhole cover and outside plaster in C. M. 1:3, inside plaster finished with floating coat of neat cement, vata in CM1:1 around pipe entering and leaving the manhole and also at the junction of masonry and concrete slab providing and fixing of SFRC foot steps of approved make at every 0.30m height fixed in CM 1:3, supplying and fixing heavy duty SFRC manhole frame and cover as per IS 12592 (Part I and II) having clear opening of 560mm, including refilling of Jhir, including curing, watering, ramming, hydro testing of manhole, conveyance & cost of water, and dewatering complete as directed by the Engineer. Manhole "Type-A" of depth 0.90 m	1.00 Nos.		15550.00	15550.00
22	R-17.42.2 Providing and constructing extra depth of manhole "Type-A" for depth beyond 0.90 m and upto 1.65 m with RR stone masonry including 20mm plaster inside and outside as per drawing and direction of Engineer.	1.00 Mtr		8380.00	8380.00
	Total			Say Rs.	40 00 Lacs

Item No.	Particulars	Qty.	Unit	Rate	Amount
----------	-------------	------	------	------	--------

Terms and Condition :-

सभी प्रकार के कर (टैक्स) संवेदक द्वारा ही वहन किये जायेंगे।

कार्य स्थल पर श्रमिक व सामग्री की सुरक्षा की जिम्मेवारी संवेदक की होगी।

जी.सारणी में वर्णित कार्यों के अतिरिक्त व अधिक कार्य संवेदक द्वारा दी गई दरों के आधार पर करवाये जा सकेंगे।

कार्य स्थल पर कार्य सम्बन्धित सूचनाएं दर्शाने वाला बोर्ड संवेदक को स्वयं के स्तर पर लगाना होगा।

टंकण त्रुटी की अवस्था में सम्बन्धित रेट मान्य होगी।

कार्य करने से पूर्व एवं कार्य करने के पश्चात कार्य स्थल की फोटो/विडियोग्राफी सीडी आवश्यक रूप से कार्यालय में जमा कराने होंगे।

7. दोष निवारण अवधि नियमानुसार रहेगी।

8. सशर्त निविदा स्वीकार नहीं होगी।

9. निष्पादन सुरक्षा राशि 10 प्रतिशत मय अनुबन्ध के जमा कराना होगा।

S/RE

We hereby agree to do the above work @ _____ Above/below the "G" Schedule

(Signature of Contractor)

JODHPUR NAGAR NIGAM JODHPUR

G-SCHEDULE

NIT No. date

Last Date of Sale :-

Date of Receipt :-

Copy issued to M/s

Name of work : बाई चं. 7 में जाला कवरिंग व पुलिय मरम्मत का कांफ

Sr No.
Earnest Money : Rs.
CR No. Dated.

BSR : PWD BUILDING BSR 2019 & RUIDP BSR 2022

S.No	Item No.	Particulars	Qty.	Unit	Rate	Amount
1	R-17.1.1	Earth work for Sewer line and Manhole in excavation in foundation, trenches manholes, road side chambers, etc. including dressing of sides and ramming of bottoms, including getting out the excavated material, refilling after laying pipe/ foundation and disposal of surplus excavated material at a lead upto 50m suitable site as per direction of Engineer for following depths, below natural ground / Road top level including allowances for any additional excavation beyond the drawings (measurement for payment to be as per standard drawings), re-handling of material/earth to complete the task. In all types soils/ saturated soil such as moorum, sand, sandy silt, clay, black cotton soil, kankar, etc.	1.00	Cum	274.50	274.50
	17.1.1.1	Depth upto 1.5 m	1.00	Cum	19.20	19.20
	17.1.1.2	Add extra for over all depth of excavation above 1.5 m and upto 3.0 m over item no 17.1.1.1	1.00	Cum	43.90	43.90
	17.1.1.3	Add extra for over all depth of excavation above 3.0 m and upto 4.5 m over item no 17.1.1.1	1.00	Cum	76.90	76.90
	17.1.1.4	Add extra for over all depth of excavation above 4.5 m and upto 6.0 m over item no 17.1.1.1	1.00	Cum	118.00	118.00
2	17.1.2.1	Earth work for Sewer line and Manhole in excavation in foundation, trenches manholes, road side chambers etc. including dressing of sides and ramming of bottoms, including getting out the excavated material, refilling after laying pipe/ foundation and disposal of surplus excavated material at a lead upto 50m suitable site as per direction of Engineer for following depths, below natural ground / Road top level including allowances for any additional excavation beyond the drawings (measurement for payment to be as per standard drawings), re-handling of material/earth to complete the task. In ordinary rock. Depth upto 1.5 m	1.00	Cum	1172.00	1172.00
	17.1.2.2	Add extra for over all depth of excavation above 1.5 m and upto 3.0 m over item no 17.1.2.1	1.00	Cum	82.00	82.00
	17.1.2.3	Add extra for over all depth of excavation above 3.0 m and upto 4.5 m over item no 17.1.2.1	1.00	Cum	187.50	187.50
3	R-17.3.1	Providing and fixing CLOSE timbering in trenches of sewer line and manholes including strutting, shoring and packing cavities (wherever required) complete. (Measurements to be taken of the face area timbered) for following depth below NGL. Depth upto 3.0 m	1.00	Sqm	136.00	136.00
4	R-17.8	Dismantling of flexible pavements for sewer line and manholes and disposal of dismantled materials up to a lead of 50 metres as directed by Engineer including allowances for any additional dismantling beyond the drawings (measurement for payment to be as per standard drawings), re-handling of material/earth to complete the task	1.00	Cum	493.50	493.50
	17.8.1	Bituminous courses	1.00	Cum	343.50	343.50
	17.8.2	Granular courses	1.00	Cum	343.50	343.50

S.No	Item No.	Particulars	Qty.	Unit	Rate	Amount
5	R-17.9	Dismantling of cement concrete pavement for sewer line and manholes by mechanical means using pneumatic tools, cutting the peripheral edge by CC cutter, breaking to pieces not exceeding 0.02 cum in volume and stock piling at designated locations and disposal of dismantled materials up to a lead of 1000 metres including allowances for any additional dismantling beyond the drawings (measurement for payment to be as per standard drawings), rehandling of material/earth to complete the task.	1.00	Cum	1170.00	1170.00
6	B-1.29.2	Pumping out water caused by springs, tidal or river seepage, broken water main or drains and the like with pumping set of following H.P. including P.O.L./Power consumption etc. complete. 10 to 19 H.P.	1.00	Hrs	214.00	214.00
7	R-4.25	Providing Barricading for Trenches using 80 - 100 mm dia Wooden Ballies as vertical post, atleast 1.5m above ground level and atleast 30-45 cm below ground level at a spacing of 3 m. Two rows of PVC Tape (preferably red in colour) strip barricading horizontal strip securely tied by the vertical members. Vertical members shall be painted in red and white colour. Rate is inclusive removal and cleaning of site complete in all respect	1.00	Mtr	104.50	104.50
8	R-17.18.	Providing at site, lowering & laying in trenches, aligning & jointing of RCC pipes NP4 class (with s/s ends) IS: 458 - 2003 (amended up to date) marked and pipes from 300 mm and upto 1800 mm manufactured through vertical / vibrated casting process at all depths with Rubber gaskets (EPDM/SBR) for sewer lines as per IS: 5382 (including cost of Rubber gaskets, lubricants) as per drawing, sectional hydro testing of the sewer pipe line (including cost and conveyance of water to site for testing) etc., complete as per specification and / or as directed by Engineer. Note : E/w to be measured and paid separately. Length of pipe shall be measured in between the outer wall of two manholes / Inspection chambers. Pipe in the manhole/inspection chamber's wall shall deemed to be included in the item of manhole/inspection chamber shall not be payable.	1.00	Mtr	6070.00	6070.00
	17.18.12	a) 800 mm internal diameter	1.00	Mtr	3790.00	3790.00
	17.18.9	b) 600 mm internal diameter	1.00	Mtr	2715.00	2715.00
	17.18.7	c) 450 mm internal diameter	1.00	Mtr	1158.00	1158.00
	17.18.4	d) 300 mm internal diameter	1.00	Mtr	1158.00	1158.00
9	R-17.30	Providing granular bedding having width = outer dia of pipe (Bc) + 500mm, thickness below pipe = 0.25Bc or 100mm (whichever is higher) and haunching = 0.5Bc, with graded hard crusher broken stone of 100% passing through 20mm sheive, 20 to 50 % passing through 10mm sheive and 100 % retain on 6.3mm sheive, laying in layers of thickness 10/15cm including ramming, consolidation etc complete for all type of pipes of following sizes as per drawing and or as directed by Engineer.	1.00	Mtr	653.00	653.00
	17.30.12	a) 800 mm internal diameter	1.00	Mtr	467.50	467.50
	17.30.10	b) 600 mm internal diameter	1.00	Mtr	335.50	335.50
	17.30.8	c) 450 mm internal diameter	1.00	Mtr	199.50	199.50
	17.30.5	d) 300 mm internal diameter	1.00	Mtr	199.50	199.50
10	R-32.3.3	Cement plastering including T&P, scaffolding, material and complete labpour, including cost of water, curing, racking of joints etc. with 20 mm cement plaster of mix : 1:6 (1 cement : 6 fine/ coarse sand)	1.00	Sqm	264.00	264.00
11	B-6.27.1	Supplying and fixing Soorsagar Bhura or Equivalent ashlar sills, lintels and dassa, bearing, bed & top surface made perfectly even, jambs, skirting steps etc. rough dressed : Upto 15 cm. thick	1.00	Cum	4473.00	4473.00
12	R-25.1.1	Random rubble masonry with hard stone in foundation and plinth : Cement mortar 1:6 (1 cement : 6 coarse sand)	1.00	Cum	4245.00	4245.00
13	R-25.1.1	Random rubble masonry with hard stone in foundation and plinth : Cement mortar 1:6 (1 cement : 6 coarse sand) Extra for random rubble masonry with hard stone in superstructure above plinth level and upto two stories.	1.00	Cum	5135.00	5135.00

S.No	Item No.	Particulars	Qty.	Unit	Rate	Amount
14	R 17 80 1	Supplying & fixing 560mm dia SFRC manhole frame & cover as per IS 12592 2002 in existing manholes including grouting the frame in PCC M 15 complete in all respect as directed by the Engineer. HD-20	1.00	Nos	2685.00	2685.00
15	R 9 1	Providing and laying lean cement concrete 1:4:8 in Sub- base over a prepared sub grade with coarse and fine aggregate conforming to IS: 383, the size of coarse aggregate not exceeding 25 mm, aggregate cement ratio not to exceed 15:1, aggregate gradation after blending to be as per table 600-1, cement content not to be less than 150 kg/ cum, optimum moisture content to be determined during trial length construction, concrete strength not to be less than 10 Mpa at 7 days, mixed in concrete mixer, laid manually, compacted with surface vibrator, finishing and curing complete as per clause 601, 112 of MoRT&H specification including all material, labour, machinery, lighting, guarding and maintenance of diversion.	1.00	Cum	2775.00	2775.00
16	R 9 5 1	Providing and laying un-reinforced, dowel jointed, plain cement concrete mix With Concrete Mixer & vibrator pavement over a prepared sub base with 43 grade cement , coarse and fine aggregate conforming to IS: 383, maximum size of coarse aggregate not exceeding 25 mm, mixed as per approved mix design, laid, spread, compacted and finished in a continuous operation including provision of contraction, expansion, construction and longitudinal joints, joint filler, separation membrane, sealant primer, joint sealant, debonding strip, admixtures (if required) as approved, curing compound, finishing to lines and grades complete as per drawing and as per clause 602, 112 of MoRT&H specification including all material, labour, machinery, lighting, guarding and maintenance of diversion. PCC M-20	1.00	Cum	5550.00	5550.00
17	R 17 85	Emptying of domestic septic tank/ soakage well etc, disposing of sludge within a lead of 5km and taking out sewage by mechanical means including refilling with local earth, ramming and compaction in layers, cleaning of site.	1.00	Nos	4630.00	4630.00
18	R 4 1 3	Earth filling with available surplus soil excavated from foundations and taken only from outside of building plinth in layers not exceeding 20cm in depth, consolidating each deposited layer including ramming and watering and consolidation with lead up to 50 m and lift upto 1.5 m.	1.00	Cum	144.00	144.00
19	R 1 1 1	Carriage of Materials by mechanical transport including loading, unloading and stacking : Earth	1.00	Cum	245.95	245.95
20	R 30 35	Random rubble dry stone Kharanja (soling) under floor.	1.00	Cum	1838.50	1838.50
21	R 17 42	Providing and constructing of RR stone masonry circular manholes of "Type-A" with internal dia 0.90m and depth upto 1.65m having 300mm thick RR stone masonry wall in cement sand mortar 1:4, including concreting PCC M-10 grade (1:4:8) for 225mm thick foundation including curing compaction and form work etc complete, PCC M15 for benching and channel portion, RCC M20 for 200mm thick cover slab including reinforcement, PCC M20 for fixing the manhole frame and cover using stone aggregate 20mm nominal size, 20mm thick inside and outside plaster in C. M. 1:3, inside plaster finished with floating coat of neat cement, vata in CM1:1 around pipe entering and leaving the manhole and also at the junction of masonry and concrete slab, providing and fixing of SFRC foot steps of approved make at every 0.30m height fixed in CM 1:3, supplying and fixing heavy duty SFRC manhole frame and cover as per IS 12592 (Part I and II) having clear opening of 560mm, including refilling of Jhiri, including curing, watering, ramming, hydro testing of manhole, conveyance & cost of water, and dewatering complete as directed by the Engineer. Manhole "Type-A" of depth 0.90 m	1.00	Nos.	15550.00	15550.00
22	R 17 42 2	Providing and constructing extra depth of manhole "Type-A" for depth beyond 0.90 m and upto 1.65 m with RR stone masonry including 20mm plaster inside and outside as per drawing and direction of Engineer.	1.00	Mtr	8380.00	8380.00
		Total				75739.45
					Say Rs.	22.00 Lacs

SANCTION No. _____ Date _____
Rs. _____
CHE. HEAD
1.00 Nos. 15550.00 15550.00
EXECUTIVE ENGINEER COMPUTER
MUNICIPAL CORPORATION 8380.00 8380.00
75739.45

S.No	Item No.	Particulars	Qty.	Unit	Rate	Amount
------	----------	-------------	------	------	------	--------

Terms and Condition :-

1. सभी प्रकार के कर (टैक्स) संवेदक द्वारा ही वहन किये जायेंगे।
2. कार्य स्थल पर श्रमिक व सामग्री की सुरक्षा की जिम्मेवारी संवेदक की होगी।
3. जी.सारणी में वर्णित कार्यों के अतिरिक्त व अधिक कार्य संवेदक द्वारा दी गई दरों के आधार पर करवाये जा सकेंगे।
4. कार्य स्थल पर कार्य संबंधित सूचनाएं दर्शाने वाला बोर्ड संवेदक को स्वयं के स्तर पर लगाना होगा।
5. टंकण त्रुटी की अवस्था में सम्बन्धित रेट मान्य होगी।
6. कार्य करने से पूर्व एवं कार्य करने के पश्चात कार्य स्थल की फोटो/विडियोग्राफी सीडी आवश्यक रूप से कार्यालय में जमा कराने होंगे।
7. दोष निवारण अवधि नियमानुसार रहेगी ।
8. सशर्त निविदा स्वीकार नहीं होगी ।
9. निष्पादन सुरक्षा राशि 10 प्रतिशत मय अनुबन्ध के जमा कराना होगा ।



I/We hereby agree to do the above work @ _____ Above/below the "G" Schedule

(Signature of Contractor)

JODHPUR NAGAR NIGAM SOUTH

G-SCHEDULE

NIT No. date

Sr No.

Last Date of Sale :-

Earnest Money : Rs.

Date of Receipt :-

CR No. Dated.

Copy issued to M/s

Name of Work :- वार्ड 6 से 21 में विभिन्न पार्को में नवीनीकरण व गरमत्त कार्य (वार्षिक अनुबंध)


Ruidp 2022 & PWD 2017

Sno	Particulars	Quantity	Unit	Rate	Amount
1	Dismantling of existing structures like culverts, bridges, retaining walls, CC road and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts and lead of 50 metres as directed by Engineer.				
	Lime Concrete, cement concrete grade M-10 (1:5:10) and below	1	cum	365	365
2	Cement Concrete Grade M-15 and above and PCC blocks	1	cum	620	620
3	Earth work in excavation in foundation, trenches etc. including dressing of sides and ramming of bottoms, including getting out the excavated material, refilling after laying pipe/ foundation and disposal of surplus excavated material at a lead upto 50m suitable site as per direction of Engineer for following depths, below natural ground / Road top level.	1	cum	210.5	210.5
4	Carriage of Materials by mechanical transport including loading, unloading and stacking ::10km	1	Cum.	245.95	245.95
5	Random rubble masonry with hard stone in foundation and plinth : Cement mortar 1:6 (1 cement : 6 coarse sand)	1	Cum	4245	4245
6	Extra for random rubble masonry with hard stone in superstructure above plinth level and upto two stories.	1	Cum	5135	5135
7	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering - All work upto plinth level :				
8	1:5:10 (1 cement : 5 fine/ coarse sand : 10 graded stone aggregate 40 mm nominal size)	1	Cum	4075	4075
9	Providing and fixing of 60mm thick precast cement concrete interlocking paver block casted with rubber moulds in approved reflective colour and design having minimum compressive strength of 300 kg/ sq cm . The CC paving blocks be laid on average 50mm thick bed of coarse sand and the joint is to be filled with fine sand. Laying procedure on compacted sub-base as defined. Complete job is to be executed as per the instruction of Engineer incharge. The rates to be inclusive of all lead & Lifts etc. complete as per specifications	1	Sqm	664	664
10	Providing and fixing steel gate grating and grills made of angles, tees, square bars or other flats black pipe with holdfast and fittings complete as per design and drawing including cutting welding and fabrication with priming coat of red oxide.	1	Kg	91	91
11	Add extra if square, rectangular hollow tubular sections are used.	1	Kg	12	12
12	Supply and fixing Jodhpur sand stone Machine cut Kerb stone (10cm wide 40 cm. height) fixed in white cement sand mortar 1:4 with pigment including EarthWork.	1	rm.	714	714

13	Providing & laying interlocking terrzo cloured blockplastic moulded.80 mm thickness having min.crushing strangth 40-N/mm2 laid over 40 mm thickriver sand bed complete as per drawing and pproved by Engineer In Charge , Complete with all respect .	1	Sqm	802	802
14	Pointing on stone masonry in cement sand mortar 1:3 (1-Cement:3-Sand) :Flush/ Ruled pointing	1	Sqm	205	205
15	Cement concrete flooring grade 1:2:4 (1-Cement:2-Coarse sand:4-graded stone aggregate) rounding off edges etc. but excluding the cost of nosing of steps etc. complete IS 2571-1970 :75 mm thick with 20 mm thick nominal size aggregate	1	Sqm	540	540
16	Finishing wall with water proofing cement paint of approved brand and manufacture and or required shade to give an even shade including all scaffolding: New work (Three or more coats).	1	Sqm	85.4	85.4
17	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : One or more coats on old work.	1	Sqm	67	67
18	Painting two coats on specified surface with synthetic enamel paintof approved brand and shade, after thorough cleaning and necessary filling to give even shade as per clause 803 of MoRT&H Specification including all material, labour.	1	Sqm	84.2	84.2
19	Uprooting weeds from the lawn plots and trenched area after 10 to 15 days of its flooding with including disposal of uprooted vegetation.	1	Sqm	4.1	4.1
					18165.2
				say rs.40.00 lac	

Terms and Condition :-

1. सभी प्रकार के कर (टैक्स) संवेदक द्वारा ही वहन किये जायेंगे।
2. कार्य स्थल पर श्रमिक व सामग्री की सुरक्षा की जिम्मेवारी संवेदक की होगी।
3. जी.सारणी में वर्णित कार्यों के अतिरिक्त व अधिक कार्य संवेदक द्वारा दी गई दरों के आधार पर करवाये जा सकेंगे।
- 4.कार्य स्थल पर कार्य सम्बंधित सूचनाएं दर्शाने वाला बोर्ड संवेदक को स्वयं के स्तर पर लगाना होगा।
- 5.टंकण त्रुटी की अवस्था में सम्बन्धित रेट मान्य होगी।
6. कार्य करने से पूर्व एवं कार्य करने के पश्चात कार्य स्थल की फोटो/विडियोग्राफी सीडी आवश्यक रूप से कार्यालय में जमा कराने होंगे।
7. दोष निवारण अवधि नियमानुसार रहेगी ।
- 9 सशर्त निविदा स्वीकार नहीं होगी ।
- 10 निष्पादन सुरक्षा राशि 10 प्रतिशत मय अनुबन्ध के जमा कराना होगा ।


EXECUTIVE ENGINEER
NAGAR NIGAM, JODHPUR.

I/We hereby agree to do the above work @ _____ Above/below the "G" Schedule

(Signature of Contractor)

JODHPUR NAGAR NIGAM SOUTH G-SCHEDULE

NIT No. date

Last Date of Sale :-

Date of Receipt :-

Copy issued to M/s

Sr No.

Earnest Money : Rs.

CR No. Dated.

Name of Work :- नगर निगम जोधपुर दक्षिण के क्षेत्राधिकार में विभिन्न स्थानों पर मरम्मत, चित्रकारी व माण्डने का कार्य


Ruidp 2022 & PWD 2017

Sno	Particulars	Quantity	Unit	Rate	Amount
1	Random rubble masonry with hard stone in foundation and plinth : Cement mortar 1:6 (1 cement : 6 coarse sand) cum 3190.00	1	Cum	4245	4245
2	Extra for random rubble masonry with hard stone in superstructure above plinth level and upto two stories.	1	Cum	5135	5135
3	Chequered terrazo tiles 22 mm thick with graded marble chips of size up to 6 mm in floors jointed with neat cement slurry mixed with pigment to match the shade of the tiles including rubbing and polishing complete on 20 mm thick bed of cement mortar 1:4 (1 cement :4 coarse sand) : Medium shade using 50% white cement, 50% ordinary cement.	1	Sqm	891	891
4	Pointing on stone masonry in cement sand mortar 1:3 (1-Cement:3- Sand) :Flush/ Ruled pointing	1	Sqm	205	205
5	Cement concrete flooring grade 1:2:4 (1-Cement:2-Coarse sand:4-graded stone aggregate) rounding off edges etc. but excluding the cost of nosing of steps etc. complete IS 2571-1970 :75 mm thick with 20 mm thick nominal size aggregate	1	Sqm	540	540
6	Finishing wall with water proofing cement paint of approved brand and manufacture and or required shade to give an even shade including all scaffolding: New work (Three or more coats).	1	Sqm	85.4	85.4
7	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : One or more coats on old work.	1	Sqm	67	67
8	Painting two coats on specified surface with synthetic enamel paint of approved brand and shade, after thorough cleaning and necessary filling to give even shade as per clause 803 of MoRT&H Specification including all material, labour.	1	Sqm	84.2	84.2
					11252.6
H-Schedule					
1	Beautification of walls, circles, govt. building etc. by traditional cultural designing, different mandana, rangoli designing to provide aesthic value. (With high performance coatings of water based acrylic polyurethale enamel.	1	sqft		0
				Say Rs.10.00 lac	

Terms and Condition :-

- सभी प्रकार के कर (टैक्स) संवेदक द्वारा ही वहन किये जायेंगे।
- कार्य स्थल पर श्रमिक व सामग्री की सुरक्षा की जिम्मेवारी संवेदक की होगी।

3. जी.सारणी में वर्णित कार्यों के अतिरिक्त व अधिक कार्य संवेदक द्वारा दी गई दरों के आधार पर करवाये जा सकेंगे।
4. कार्य स्थल पर कार्य सम्बंधित सूचनाएं दर्शाने वाला बोर्ड संवेदक को स्वयं के स्तर पर लगाना होगा।
5. टंकण त्रुटी की अवस्था में सम्बन्धित रेट मान्य होगी।
6. कार्य करने से पूर्व एवं कार्य करने के पश्चात कार्य स्थल की फोटो/विडियोग्राफी सीडी आवश्यक रूप से कार्यालय में जमा कराने होंगे।
7. दोष निवारण अवधि नियमानुसार रहेगी।
9. सशर्त निविदा स्वीकार नहीं होगी।
10. निष्पादन सुरक्षा राशि 10 प्रतिशत मय अनुबन्ध के जमा कराना होगा।


EXECUTIVE ENGINEER
NAGAR NIGAM, JODHPUR.

I/We hereby agree to do the above work @ _____ Above/below the "G" Schedule
& H-Schedule (1)

(Signature of Contractor)