

कार्यालय जोधपुर नगर निगम, दक्षिण

क्रमांक:- विकास/तृतीय/दक्षिण/2022-23/ 411

दिनांक:- 28/7/2022

-:: निविदा सूचना::-

(यू.बी. संख्या..DLB2223WSOB12543.....)

नगर निगम जोधपुर की ओर से निम्नलिखित कार्य हेतु भारत सरकार एवं राज्य सरकार के विभिन्न विभागों/स्वायत्तशासी/निगमों/बोर्डों/राजकीय उपक्रमों में पंजीकृत ए. ए व ए. श्रेणी में पंजीकृत तथा नगर निगम जोधपुर में निर्धारित श्रेणी में पंजीकृत नियमानुसार योग्य संवेदको से निर्धारित प्रपत्र में मुहरबन्द निविदाएं आमंत्रित की जाती है। निविदा दिनांक 5.8.02 को 12.30 बजे तक बेची जाकर दिनांक 5.8.02 को दोपहर 2.00 बजे तक प्राप्त कर 3.00 बजे उपस्थित संवेदको के समक्ष खोली जायेगी। अन्य विवरण एवं शर्तें निविदा प्रपत्र कार्यालय समय में कार्यालय में देखे जा सकते हैं। sppp.raj.nic.in एवं जोधपुर नगर निगम की वेबसाईट urban.rajasthan.gov.in/mcjs पर देखी जा सकती है।

क्र. सं.	कार्य का नाम	अनु. लागत (राशि लाखों में)	धरोहर राशि	निविदा शुल्क	कार्य पूर्ण करने की अवधि
01	Construction of Bird House at Nehru Park	4.00	8000/-	500/-	1 माह

नोट :- (1) कार्य शुरू करने से पूर्व व कार्य पूर्ण करने के पश्चात् कार्य स्थल की फोटो/ विडियोग्राफी सी.डी. आवश्यक रूप से प्रस्तुत करें। (2) सशर्त निविदा स्वीकार नहीं होगी। (3) दोष निवारण अवधि नियमानुसार होगी। (4) धरोहर राशि के डिमाण्ड ड्राफ्ट की वैधता निविदा खोलने की तारीख से निविदा की वैधता अवधि तक होनी अनिवार्य है अन्यथा निविदा कॉपी निरस्त की जा सकती है। (5) निविदा कॉपी बाबत आवेदन पत्र के साथ पंजीयन प्रमाण-पत्र संलग्न करना आवश्यक है, अन्यथा निविदा कॉपी जारी नहीं की जायेगी। (6) आयुक्त नगर निगम जोधपुर के आदेश क्रमांक 9836 दिनांक 07.02.2020 एवं 9975 दिनांक 14.07.2020 के अनुसार पंजीयन रिव्यू आदेश के तहत निविदा स्वीकार/अस्वीकार की जायेगी। (7) श्रीमान् निदेशक, स्वायत्त शासन विभाग राजस्थान जयपुर के आदेश क्रमांक 144612-825 दिनांक 22.11.2021 की पालना में वित्त विभाग की अधिसूचना दिनांक 22.10.2021 अनुसार आर.टी.पी.पी. नियम 2013 में Additional Performance Security के लिए नियम 75 -ए के अनुसार Additional Performance Security जमा करवानी होगी।

↓
आयुक्त

जोधपुर नगर निगम दक्षिण

दिनांक:- 28/7/2022

क्रमांक:- 412 to 418

प्रतिलिपी :- सूचनार्थ एवं आवश्यक कार्यवाही हेतु।

1. श्रीमान् जिला कलेक्टर महोदय, जोधपुर।
2. निदेशक/अधीक्षण अभियन्ता, स्थानीय निकाय विभाग, जयपुर।
3. अधीक्षण अभियन्ता/अधिशाशी अभियन्ता, सा.नि.वि./जोधपुर विकास प्राधिकरण जोधपुर।
4. लेखाधिकारी, जोधपुर नगर निगम दक्षिण।
5. उक्त निविदा सूचना दैनिक प्रतिनिधि को वास्ते नियमानुसार समाचार पत्र में प्रकाशन हेतु।
6. श्री रामेश्वर गहलोत, प्रोग्रामर नगर निगम जोधपुर दक्षिण को भेजकर लेख है कि ई-निविदा सूचना urban.rajasthan.gov.in/mcjs एवं sppp.rajasthan.gov.in, पर अपलोड करें।
7. सूचना पट्ट जोधपुर नगर निगम दक्षिण।

↓

आयुक्त

जोधपुर नगर निगम दक्षिण

OFFICE OF THE MUNICIPAL CORPORATION, JODHPUR

G-SCHEDULE

NIT No. **411** Date **28/7/2022**

Sr No. **(1)**

Last Date of Sale :- **5.8.022**

T. Fee **.....** Est. Money Rs. **.....**

Date of Receipt :- **5.8.022**

CR No. **.....** Dated. **.....**

Copy issued to M/s **.....**

Rate Based on RUIDP 2022

Name of Work - construction of bird house at Nehru Park

S.No.	Particulars	Qty.	Unit	Rate	Amount
1	Earth work in excavation in foundation, trenches etc. including dressing of sides and ramming of bottoms, including getting out the excavated material, refilling after laying pipe/ foundation and disposal of surplus excavated material at a lead upto 50m suitable site as per direction of Engineer for following depths, below natural ground / Road top level. In all types soils/ saturated soil such as moorum, sand, sandy silt, clay, black cotton soil, kankar, etc. Depth upto 1.5 m	6	cum	210.5	1263
2	Centring and shuttering with plywood or steel sheet upto two stories or height upto 7.5 metre above plinth level including strutting, propping etc. and removal of form for :				
a	Foundations, footings, bases of columns, etc. for mass concrete.	2.7	cum	220	594
b	Columns, Pillars, Piers, Abutments, Posts and Struts.	9	cum	345	3105
c	Suspended floors, roofs, landings, balconies and access platform.	65.95	sqm	403.5	26610.825
3	Providing and laying in position specified grade of reinforced cement concrete excluding the cost of centring, shuttering, finishing and reinforcement - All work upto plinth level : 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20 mm nominal size)	1.0125	cum	6200	6277.5
4	Reinforced cement concrete work in walls (any thickness), including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts etc. upto two stories excluding cost of centring, shuttering, finishing and reinforcement : 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20 mm nominal size)	1.0125	cum	6780	6864.75
5	Reinforced cement concrete work in beams, suspended floors, roofs having slope upto 15° landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases upto two stories excluding the cost of centring, shuttering, finishing and reinforcement:M-20 Grade Concrete (1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20 mm nominal size) -As per design mix)	6.5625	cum	7030	46134.375
6	Providing and fabricating reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding (including cost of binding wire) all complete up to floor three level. Cold twisted deformed bars (IS : 1786)	500	kg	64.2	32100
7	Providing and laying in position cement concrete including curing compaction etc. of specified grade excluding the cost of centering and shuttering All up to plinth level IS 456-2000: 1:4:8 (1Cement :4 Course Sand :8 Graded stone aggregate 40 mm nominal size (Crusher Broken)	10	cum	4340	43400
8	Random rubble masonry with hard stone in foundation and plinth : Cement mortar 1:6 (1 cement : 6 coarse sand)	5	cum	4225	21125
9	Brick work in partition in super structure up to third storey 7 Cm. thick (brick on edges) using bricks of class designation 75 with nominal hoop reinforcement (2 Nos 6mm MS bar) at every fourth course in Cement sand mortar 1:4 (1-Cement:4-coarse sand).	3.5	sqm	421	1473.5
10	Distemping with oil bound washable distemper of approved brand and manufacture to give an even shade including all scaffolding: New work (two or more coats) over and including scrapping and priming coat with cement primer.	25	sqm	125	3125

	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering - All work upto plinth level : 1:1½:3 (1 Cement : 1½ coarse sand : 3 graded stone aggregate 20 mm nominal size).	4	cum	5810.00	23240
12	Providing precast cement concrete Jali 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 6mm nominal size) reinforced with 1.6 mm dia mild steel wire including centring and shuttering, roughening cleaning, fixing and finishing in cement mortar 1:3 (1 cement: 3 fine sand) etc. complete excluding plastering of the jambs, sills and soffits. 50 mm thick	120	sqm	1113	133560
13	Plaster on new surface on walls in cement sand mortar 1:4 including raking of joints etc. complete fine finish: 20 mm thick.	200	sqm	222	44400
14	Marble stone flooring table rubbed, 18-20 mm thick over 20 mm (Av.) thick base of CM 1:4 (1-Cement:4-coarse sand) jointing with white cement mortar 1:2 (1-White cement:2-marble dust) with pigment to match the shade of the marble slab including grinding rubbing and polishing complete IS 1130-1969.Rajnagar 2nd quality with light spots and streaks. (C) Size upto 1501 to 3600 Cm2	2.25	sqm	899	2022.75
15	Cement concrete flooring 1:2:4 (1 cement : 2 coarse sand : 4 graded 20mm nominal size stone aggregate) finished with a floating coat of neat cement including cement slurry, but excluding the cost of nosing of steps etc. complete. 75mm thick	10	sqm	721	7210
Total					402505.7

Terms and Condition :-

1. सभी प्रकार के कर (टैक्स) संवेदक द्वारा ही वहन किये जायेंगे।
2. कार्य स्थल पर श्रमिक व सामग्री की सुरक्षा की जिम्मेवारी संवेदक की होगी।
3. जी.सारणी में वर्णित कार्यों के अतिरिक्त व अधिक कार्य संवेदक द्वारा दी गई दरों के आधार पर करवाये जा सकेंगे।
4. कार्य स्थल पर कार्य सम्बंधित सूचनाएं दर्शाने वाला बोर्ड संवेदक को स्वयं के स्तर पर लगाना होगा।
5. टंकण त्रुटी की अवस्था में सम्बंधित रेट मान्य होगी।
6. कार्य करने से पूर्व एवं कार्य करने के पश्चात कार्य स्थल की फोटो/विडियोग्राफी सीडी आवश्यक रूप से कार्यालय
7. दोष निवारण अवधि नियमानुसार रहेगी।
8. दरें 4 माह तक मान्य रहेगी
9. सशर्त निविदा स्वीकार नहीं होगी।



EXECUTIVE ENGINEER
NAGAR NIGAM SOUTH JODHPUR.

I/We hereby agree to do the above work @ _____ Above/below the "G" Schedule.

(Signature of Contractor)