

## कार्यालय जोधपुर नगर निगम-दक्षिण

क्रमांक :- न.नि.जो./दक्षिण/द्वितीय/विकास/2022-23/868

दिनांक :- 7.10.2022

## :: अल्पकालिन ई-निविदा सूचना ::

नगर निगम जोधपुर की ओर से निम्नलिखित कार्यो हेतु भारत सरकार एवं राज्य सरकार के विभिन्न विभागों/स्वायतशासी/निगमों/बोर्डों/राजकीय उपक्रमों में पंजीकृत ए.ए व ए. श्रेणी में पंजीकृत तथा नगर निगम जोधपुर दक्षिण में निर्धारित श्रेणी में पंजीकृत नियमानुसार योग्य संवेदको से निर्धारित प्रपत्र में मुहरबन्द ई-निविदाएं आमंत्रित की जाती है।

## महत्वपूर्ण दिनाकों का विवरण

विवरण	दिनांक
ऑन लाईन निविदा फार्म जमा कराना प्रारम्भ होने की दिनांक व समय	08.10.2022/12:30 PM
ऑन लाईन निविदा फार्म जमा कराने की अन्तिम दिनांक व समय	18.10.2022/12:30 PM
ऑन लाईन निविदा खोलने की तारीख	— " — / 3.00 PM
निविदा शुल्क/धरोहर राशि की मूल प्रति अधीक्षण अभियन्ता कार्यालय में जमा कराने की दिनांक व समयावधि	— " — / 2.00 PM

निविदा का विवरण निम्न प्रकार है :-

क्र. सं.	कार्य का नाम	कार्य की अनुमानित लागत (लाखों में)	धरोहर राशि रुपये	निविदा शुल्क	कार्य पूर्ण करने की अवधि
1.	Repair of Sewer line in Front of AFRI and Near Navdurga Colony Gate Jodhpur	62.50	125000/-	1000/-	03 माह
2	Repair of Sewer line in Front of Bhagat ki kothi Railway Station Jodhpur.	23.03	46060/-	500/-	03 माह

निविदा की महत्वपूर्ण शर्तें निम्नानुसार है :-

- निविदा प्रपत्रों को वेबसाईट <http://eproc.rajasthan.gov.in> से डाउनलोड किया जा सकता है। इन निविदाओं में भाग लेने वाले संवेदको को निविदा को इलेक्ट्रॉनिक फॉरमेट में वेबसाईट <http://eproc.rajasthan.gov.in> पर जमा करानी होगी।
- निविदा की प्रकिया ऑन लाईन होगी।
- निविदा हेतु पात्र संवेदको की श्रेणी -
 

किसी भी सीमा तक	- एए श्रेणी, संवेदक
रुपये 300.00 लाख तक	- ए, श्रेणी संवेदक
रुपये 150.00 लाख तक	- बी, श्रेणी संवेदक
रुपये 50.00 लाख तक	- सी, श्रेणी संवेदक
रुपये 15.00 लाख तक	- डी, श्रेणी संवेदक
- निविदा खोलने की तिथि को किसी कारणवश यदि सम्पूर्ण निविदायें नहीं खोली जा सकती है, तो उसके अगले कार्य दिवस को शेष निविदायें खोलने का कार्य जारी रखा जावेगा।

ई-निविदा प्रक्रिया -

कार्य

पोटेशियल असेसमेंट

पोस्ट क्वालीफिकेशन

सडक

150 लाख से 500 लाख तक

500 लाख से अधिक तक

अन्य निर्माण कार्य

100 लाख से 200 लाख तक

200 लाख से अधिक तक

5. निविदादाता द्वारा निविदा शुल्क, धरोहर राशि एवं प्रक्रिया शुल्क हेतु निम्नलिखित राशि कि मूल प्रति जोधपुर नगर निगम कार्यालय में नियमानुसार निविदा खोले जाने के समय से पूर्व जमा करवाना आवश्यक है। निम्नलिखित डिमांड/बैंकर चैक शुल्क ऑनलाईन निविदा फार्म जमाने की अन्तिम तिथि से पूर्व का होना आवश्यक है।

क्र. सं.	शुल्क वितरण	शुल्क	भुगतान का प्रकार	देय
1	निविदा शुल्क	उपरोक्तानुसार	डिमान्ड ड्राफ्ट/बैंकर चैक	आयुक्त जोधपुर नगर निगम-दक्षिण
2	धरोहर राशि	उपरोक्तानुसार	उपरोक्तानुसार	आयुक्त जोधपुर नगर निगम-दक्षिण
3	ई-टेण्डरिंग प्रक्रिया शुल्क	50 लाख एवं उपर 1000/- 50 लाख से नीचे 500/-	डिमान्ड ड्राफ्ट/ बैंकर चैक	MD RISL, JAIPUR

6. प्रदत्त दरें निविदा खोलने की दिनांक से 90 दिवसों तक निविदा स्वीकृति हेतु मान्य (Valid) रहेगी। यदि निविदाकर्ता उस अवधि में अपनी निविदा अथवा शर्तों में किसी प्रकार का संशोधन करता है अथवा अपनी निविदा वापस ले लेता है, तो उसकी धरोहर राशि जब्त कर ली जावेगी।
7. यदि संवेदक के नजदीकी रिश्तेदार (प्रथम रक्त सम्बन्धी व उनके पति/पत्नी) कार्य से संबंधित अधीनस्थ कार्यालय में खण्डीय लेखाकार अथवा सहायक अभियन्ता से लेकर अधीक्षण अभियन्ता स्तर का किसी भी स्तर पर पदस्थापित हो, तो उसके कार्य पर नियुक्त करने पर प्रतिबन्ध रहेगा।
8. राज्य सरकार में किसी भी अभियांत्रिकी विभाग में किसी भी इंजीनियर अथवा इंजीनियर या प्रशासनिक कार्य पर नियुक्त राजपत्रित अधिकारी राज्य की अनुमति के बिना सेवा निवृत्ति के 2 वर्ष तक संवेदक अथवा उसके कर्मचारी के रूप में कार्य नहीं कर सकेंगे। यदि संवेदक अथवा उसके कर्मचारियों में कोई ऐसा व्यक्ति जिसने राज्य सरकार की उक्त लिखित अनुमति निविदा जमा कराने से पहले अथवा संवेदक के यहां से सेवारत लेने से पहले अनुमति नहीं ली है, तो अनुबन्ध रद्द किया जा सकेगा।
9. उक्त आईटम की दोष निवारण अवधि 5 वर्ष होगी।
10. निविदा में निविदादाताओं से अंतर राशि परफोरमेंस सिक्क्यूरिटी के रूप में प्राप्त करने के पश्चात ही स्वीकृति निविदा का कार्यादेश दिया जायेगा।
11. किसी भी निविदा को स्वीकार करने एवं बिना कारण बताये निरस्त करने के समस्त अधिकार निम्नहस्ताक्षर कर्ता को रहेगा। RPWA 100 की समस्त शर्तें उस सीमा तक मान्य/लागू होंगी जिस सीमा तक के राजस्थान लोक उपापन पारदर्शिता अधिनियम 2012 एवं नियम 2013 के विरोध में नहीं हो।
12. वित्त विभाग के आदेश संख्या एफ-1)एफ.डी./जी.एफ. एण्ड ए.आर./2007 दिनांक 30.09.11 (सर्कुलर नं. 19/2011) के अनुसार 50.00 लाख रुपये से नीचे की राशि के कार्यों के लिए 500/- व 50.00 लाख रुपये एवं अधिक राशि के कार्यों के लिए 1000/- रुपये की राशि निविदा शुल्क के अतिरिक्त देनी होगी जो डिमान्ड ड्राफ्ट या बैंकर चैक के रूप में देय होगी। यह डिमान्ड ड्राफ्ट या बैंकर चैक मैनेजिंग डायरेक्ट, आर.आई.एस.एल. के पक्ष में व जयपुर में भुगतान योग्य होना चाहिए।
13. नेगोशिएशन की आवश्यकता होने पर ई-मेल अथवा पत्र द्वारा डाक से सूचित किया जायेगा।
14. ई-टेण्डरिंग के लिए निविदादाता हेतु निर्देश :-



- इन निविदाओं में दिलचस्पी लेने वाले निविदा दाता निविदा प्रपत्रों का इन्टरनेट साईट <http://www.eproc.rajasthan.gov.in> से देख/डाउनलोड कर सकते हैं।
  - निविदाओं में भाग लेने वाले निविदादाताओं को इन्टरनेट साईट <http://www.eproc.rajasthan.gov.in> पर रजिस्टर करवाना होगा। ऑन लाईन निविदा में भाग लेने के लिए डिजिटल सर्टिफिकेट है इनफोरमेशन टेक्नोलॉजी एक्ट 2000 के तहत प्राप्त करना होगा जो इलेक्ट्रॉनिक निविदा में साईन करने हेतु काम आयेगा। निविदादाता उपरोक्त डिजिटल सर्टिफिकेट सी.सी.ए. द्वारा स्वीकृत एजेन्सी से प्राप्त कर सकते हैं। जिन निविदादाताओं के पास पूर्व में वैध डिजिटल सर्टिफिकेट है, नया डिजिटल लेने की आवश्यकता नहीं है।
  - निविदादाताओं को निविदा प्रपत्र इलेक्ट्रॉनिक फॉर्म में उपरोक्त वेबसाइट पर डिजिटल साईन के साथ प्रस्तुत करना होगा। जिसके प्रस्ताव अकेले भौतिक फॉर्म में स्वीकार्य नहीं होगा।
  - इलेक्ट्रॉनिक निविदा प्रपत्रों को जमा कराने से पूर्व निविदादाता यह सुनिश्चित कर लेवे की निविदा प्रपत्रों से संबंधित सभी आवश्यक दस्तावेजों की स्कैन कॉपी निविदा प्रपत्रों के साथ अटैच कर दी गयी है।
  - कोई भी टेण्डर इलेक्ट्रॉनिकली जमा कराने से किसी कारण से लेट हो जाता है तो उसका जिम्मेदार विभाग नहीं होगा।
  - टेण्डर के प्रपत्रों में आवश्यक सभी सूचियों को सम्पूर्ण रूप से भरकर ऑन लाईन दर्ज करे।
15. निविदायें राजस्थान लोक उपापन पारदर्शिता अधिनियम 2012 एवं नियम 2013 के अन्तर्गत आमंत्रित की जाती हैं। उपर अंकित समस्त प्रावधान/बंधन उस सीमा तक ही लागू होंगे जिस सीमा तक वे उस बिन्दु में उल्लेखित अधिनियम एवं नियमों के विरुद्ध नहीं हों।
  16. आयुक्त नगर निगम जोधपुर के आदेश क्रमांक 9836 दिनांक 7.2.2020 एवं 9975 दिनांक 14.7.2020 अनुसार पंजीयन रिव्यू आदेश की पालना करनी होगी।
  17. राजकीय अवकाश की स्थिति में आगामी कार्य दिवस की तिथि मान्य होगी।
  18. श्रीमान् निदेशक, स्वायत्त शासन विभाग राजस्थान जयपुर के आदेश क्रमांक 144612-825 दिनांक 22.11.2021 की पालना में वित्त विभाग की अधिसूचना दिनांक 22.10.2021 अनुसार आर.टी.पी.पी. नियम 2013 में Additional Performance Security के लिए नियम 75-ए के अनुसार Additional Performance Security जमा करवानी होगी।

  
आयुक्त

जोधपुर नगर निगम-दक्षिण



## नगर निगम जोधपुर-दक्षिण

क्रमांक:- न.नि.जो.-दक्षिण/द्वितीय/विकास/2022-23/ 868

दिनांक:- 7.10.2022

:: अल्कालीन ई-निविदा सूचना ::

(UB No. ....DLB2223W/SOB17707.....)

नगर निगम जोधपुर-दक्षिण की ओर से विभिन्न सिविल कार्यों हेतु ऑनलाईन अल्पकालीन ई-निविदाएं आमंत्रित की जाती है। ई-निविदा से संबंधित कार्यों की विस्तृत जानकारी, निविदा की शर्तें आदि <http://eproc.rajasthan.gov.in>, [www.sppp.rajasthan.gov.in](http://www.sppp.rajasthan.gov.in) एवं [www.urban.rajasthan.gov.in/mcjs](http://www.urban.rajasthan.gov.in/mcjs) पर देखी जा सकती है।

(वनिता सेठ)

महापौर

नगर निगम जोधपुर-दक्षिण

(अरुण कुमार पुरोहित)

I.A.S.

आयुक्त

नगर निगम जोधपुर-दक्षिण

दिनांक:- 7.10.2022

क्रमांक:- न.नि.जो.-दक्षिण/द्वितीय/विकास/2022-23/ 869 to 876

प्रतिलिपी :- सूचनार्थ एवं आवश्यक कार्यवाही हेतु।

1. श्रीमान जिला कलेक्टर महोदय, जोधपुर।
2. निदेशक/अधीक्षण अभियन्ता, स्थानीय निकाय विभाग, जयपुर।
3. अधीक्षण अभियन्ता/अधिशाषी अभियन्ता, सा.नि.वि./जोधपुर विकास प्राधिकरण/नगर निगम जोधपुर।
6. वरिष्ठ लेखाधिकारी, जोधपुर नगर निगम।
7. ई-निविदा राज्य स्तरीय समाचार पत्र विराट वैभव व क्षेत्रीय समाचार पत्र मरुत्रिकोण परिक्रमा को वास्ते नियमानुसार प्रकाशन हेतु।
9. श्री रामेश्वर गहलोत, प्रोग्रामर नगर निगम जोधपुर दक्षिण को भेजकर लेख है कि एवं ई-निविदा सूचना (1) [urban.rajasthan.gov.in/mcjs](http://urban.rajasthan.gov.in/mcjs) (2) [sppp.rajasthan.gov.in](http://sppp.rajasthan.gov.in) पर अपलोड करें।
10. संबंधित सहायक अभियन्ता को भेजकर लेख है कि उपरोक्त ई-निविदा के कार्यों की जी-सारणी एवं ई-निविदा सूचना <http://eproc.rajasthan.gov.in> पर अपलोड करावे।
11. सूचना पट्ट जोधपुर नगर निगम।

(अरुण कुमार पुरोहित)

I.A.S.

आयुक्त

नगर निगम जोधपुर-दक्षिण



# JODHPUR NAGAR NIGAM - SOUTH

## GSCHEDULE

NIT No. .... date .....

Last Date of Sale :-

Date of Receipt :-

Copy issued to M/s .....

Sr No. ....

Earnest Money : Rs. ....

CR No. .... Dated. ....

Name of work : Repair of Sewer line in Front of AFRI and Near Navdurga Colony Gate Jodhpur.

BSR : RUIDP BSR 2022						
S. No	Item No.	Particulars	Qty.	Unit	Rate	Amount
1	R-17.8	Dismantling of flexible pavements for sewer line and manholes and disposal of dismantled materials up to a lead of 50 metres as directed by Engineer including allowances for any additional dismantling beyond the drawings (measurement for payment to be as per standard drawings), re-handling of material/earth to complete the task				
A	17.8.1	Bituminous courses				
			400.00			
			<b>400.00</b>	<b>Cum</b>	<b>493.50</b>	<b>197400</b>
B	17.8.2	Granular courses				
			400.00			
			<b>400.00</b>	<b>Cum</b>	<b>343.50</b>	<b>137400</b>
2	R-4.25	Providing Barricading for Trenches using 80 - 100 mm dia Wooden Ballies as vertical post, atleast 1.5m above ground level and atleast 30-45 cm below ground level at a spacing of 3 m. Two rows of PVC Tape (preferably red in colour) strip barricading horizontal strip securely tied by the vertical members. Vertical members shall be painted in red and white colour. Rate is inclusive removal and cleaning of site complete in all respect				
			400.00			
			<b>400.00</b>	<b>Mtr</b>	<b>104.50</b>	<b>41800</b>
3	R-17.1.1	Earth work for Sewer line and Manhole in excavation in foundation, trenches manholes, road side chambers etc. including dressing of sides and ramming of bottoms, including getting out the excavated material, refilling after laying pipe/ foundation and disposal of surplus excavated material at a lead upto 50m suitable site as per direction of Engineer for following depths, below natural ground / Road top level including allowances for any additional excavation beyond the drawings (measurement for payment to be as per standard drawings), re-handling of material/earth to complete the task. In all types soils/ saturated soil such as moorum, sand, sandy silt, clay, black cotton soil, kankar, etc.				
A	17.1.1.1	Depth upto 1.5 m				
			2400.00			
			<b>2400.00</b>	<b>Cum</b>	<b>274.50</b>	<b>658800.00</b>
B	17.1.1.2	Add extra for over all depth of excavation above 1.5 m and upto 3.0 m over item no 17.1.1.1				
			2400.00			
			<b>2400.00</b>	<b>Cum</b>	<b>293.70</b>	<b>704880.00</b>
C	17.1.1.3	Add extra for over all depth of excavation above 3.0 m and upto 4.5 m over item no 17.1.1.1				
			2400.00			
			<b>2400.00</b>	<b>Cum</b>	<b>293.70</b>	<b>704880.00</b>

*Handwritten signature*


S. No	Item No.	Particulars	Qty.	Unit	Rate	Amount
			800.00			
			240.00			
			1040.00	Cum	318.40	331136.00
D	17.1.1.4	Add extra for over all depth of excavation above 4.5 m and upto 6.0 m over item no 17.1.1.1				
			360.00			
			360.00	Cum	351.40	126504.00
4	R-17.30	Providing granular bedding having width = outer dia of pipe (Bc) + 500mm, thickness below pipe = 0.25Bc or 100mm (whichever is higher) and haunching = 0.5Bc, with graded hard crusher broken stone of 100% passing through 20mm sheive, 20 to 50 % passing through 10mm sheive and 100 % retain on 6.3mm sheive, laying in layers of thickness 10/15cm including ramming, consolidation etc complete for all type of pipes of following sizes as per drawing and or as directed by Engineer.				
A	17.30.16	b) 1200 mm internal diameter				
			200.00			
			200.00	Mtr	1119.00	223800.00
5	R-17.18	Providing at site, lowering & laying in trenches, aligning & jointing of RCC pipes NP4 class (with s/s ends) IS: 458 - 2003 (amended up to date) marked and pipes from 300 mm and upto 1800 mm manufactured through vertical / vibrated casting process at all depths with Rubber gaskets (EPDM/SBR) for sewer lines as per IS: 5382 (including cost of Rubber gaskets, lubricants) as per drawing, sectional hydro testing of the sewer pipe line (including cost and conveyance of water to site for testing) etc., complete as per specification and / or as directed by Engineer. Note : E/w to be measured and paid separately. Length of pipe shall be measured in between the outer wall of two manholes / Inspection chambers. Pipe in the manhole/inspection chamber's wall shall deemed to be included in the item of manhole/inspection chamber shall not be payable.				
	17.18.15	a) 1200mm internal diameter	200.00			
			200.00	Mtr	11500.00	2300000.00
6	R-25.1.1	Random rubble masonry with hard stone in foundation and plinth : Cement mortar 1:6 (1 cement : 6 coarse sand)				
			8.64			
		total	8.64			
		ded	-1.32			
			7.32	Cum	4245.00	31073.40
7	R-17.80.1	Supplying & fixing 560mm dia SFRC manhole frame & cover as per IS : 12592-2002 in existing manholes including grouting the frame in PCC M-15 complete in all respect as directed by the Engineer. HD-20	6.00	Nos	2685.00	16110.00
8	R-1.1.1	Carriage of Materials by mechanical transport including loading, unloading and stacking UPTO 5 KM : Earth				
			36.00			
			265.33			
			301.33			
			800.00			
			1101.33	CUM	245.95	270872.11
9	R-30.35	Carriage of Materials by mechanical transport including loading, unloading and stacking UPTO 1.0KM : Earth				
			5098.67	Cum	152.02	775099.81



Item No.	Particulars	Qty.	Unit	Rate	Amount
4.4	Construction of embankment with approved material obtained from borrow pit with all lifts and leads, transporting to site, spreading, grading to required slope and compacting by vibratory roller 8-10 tonne to meet requirement of table 300-2 including cost of compensation for earth taken from private land complete as per MoRT&H specification clause 305. (Lead taken upto 5 km)	200.00	CUM	184.50	36900.00
11	4.5 Construction of embankment with approved materials deposited at site available from roadway cutting and excavation from drain and foundation of other structures, graded and compacting by vibratory roller 8-10 tonne to meet requirement of table 300-2 as per MoRT&H specification clause 305.	5098.67	CUM	77.50	395146.93
<b>Total</b>					<b>6246922.25</b>
					<b>SAY RS 62.50 Lac</b>

### Terms and Condition :-

1. सभी प्रकार के कर (टैक्स) संवेदक द्वारा ही वहन किये जायेंगे।
2. कार्य स्थल पर श्रमिक व सामग्री की सुरक्षा की जिम्मेवारी संवेदक की होगी।
3. जी.सारणी में वर्णित कार्यों के अतिरिक्त व अधिक कार्य संवेदक द्वारा दी गई दरों के आधार पर
4. कार्य स्थल पर कार्य सम्बंधित सूचनाएं दर्शाने वाला बोर्ड संवेदक को स्वयं के स्तर पर लगाना होगा।
5. टंकण त्रुटी की अवस्था में सम्बन्धित रेट मान्य होगी।
6. कार्य करने से पूर्व एवं कार्य करने के पश्चात कार्य स्थल की फोटो/विडियोग्राफी सीडी आवश्यक रूप से कार्यालय में जमा कराने होंगे।
7. दोष निवारण अवधि नियमानुसार रहेगी।
8. दरें 4 माह तक मान्य रहेगी
9. सशर्त निविदा स्वीकार नहीं होगी।
10. निष्पादन सुरक्षा राशि 10 प्रतिशत मय अनुबन्ध के जमा कराना होगा।

  
**EXECUTIVE ENGINEER**  
**NAGAR NIGAM, JODHPUR.**

I/We hereby agree to do the above work @ \_\_\_\_\_ Above/below the "G"

(Signature of Contractor)

# JODHPUR NAGAR NIGAM - SOUTH

## G Schedule

NIT No. .... date .....

Last Date of Sale :-

Date of Receipt :-

Copy issued to M/s .....

Sr No. ....

Earnest Money : Rs. ....

CR No. .... Dated. ....

**Name of work : Repair of Sewer line in Front of Bhagat ki kothi Railway Station  
Jodhpur.**

BSR : RUIDP BSR 2022						
S. No	Item No.	Particulars	Qty.	Unit	Rate	Amount
1	R-17.8	Dismantling of flexible pavements for sewer line and manholes and disposal of dismantled materials up to a lead of 50 metres as directed by Engineer including allowances for any additional dismantling beyond the drawings (measurement for payment to be as per standard drawings), re-handling of material/earth to complete the task				
A	17.8.1	Bituminous courses				
		Bhagat ki kothi Railway Station	200.00			
			<b>200.00</b>	<b>Cum</b>	<b>493.50</b>	<b>98700</b>
B	17.8.2	Granular courses				
		Bhagat ki kothi Railway Station	200.00			
			<b>200.00</b>	<b>Cum</b>	<b>343.50</b>	<b>68700</b>
2	R-4.25	Providing Barricading for Trenches using 80 - 100 mm dia Wooden Ballies as vertical post, atleast 1.5m above ground level and atleast 30-45 cm below ground level at a spacing of 3 m. Two rows of PVC Tape (preferably red in colour) strip barricading horizontal strip securely tied by the vertical members. Vertical members shall be painted in red and white colour. Rate is inclusive removal and cleaning of site complete in all respect				
		Bhagat ki kothi Railway Station	200.00			
			<b>200.00</b>	<b>Mtr</b>	<b>104.50</b>	<b>20900</b>
3	R-17.1.1	Earth work for Sewer line and Manhole in excavation in foundation, trenches manholes, road side chambers etc. including dressing of sides and ramming of bottoms, including getting out the excavated material, refilling after laying pipe/ foundation and disposal of surplus excavated material at a lead upto 50m suitable site as per direction of Engineer for following depths, below natural ground / Road top level including allowances for any additional excavation beyond the drawings (measurement for payment to be as per standard drawings), re-handling of material/earth to complete the task. In all types soils/ saturated soil such as moorum, sand, sandy silt, clay, black cotton soil, kankar, etc.				
A	17.1.1.1	Depth upto 1.5 m				
		Bhagat ki kothi Railway Station	1200.00			
			<b>1200.00</b>	<b>Cum</b>	<b>274.50</b>	<b>329400.00</b>
B	17.1.1.2	Add extra for over all depth of excavation above 1.5 m and upto 3.0 m over item no 17.1.1.1				
		Bhagat ki kothi Railway Station	1200.00			
			<b>1200.00</b>	<b>Cum</b>	<b>293.70</b>	<b>352440.00</b>
C	17.1.1.3	Add extra for over all depth of excavation above 3.0 m and upto 4.5 m over item no 17.1.1.1				

*br*



S. No	Item No.	Particulars	Qty.	Unit	Rate	Amount
			400.00			
			120.00			
			520.00	Cum	318.40	165568.00
D	17.1.1.4	Add extra for over all depth of excavation above 4.5 m and upto 6.0 m over item no 17.1.1.1				
			180.00			
			180.00	Cum	351.40	63252.00
4	R-17.30	Providing granular bedding having width = outer dia of pipe (Bc) + 500mm, thickness below pipe = 0.25Bc or 100mm (whichever is higher) and haunching = 0.5Bc, with graded hard crusher broken stone of 100% passing through 20mm sheive, 20 to 50 % passing through 10mm sheive and 100 % retain on 6.3mm sheive, laying in layers of thickness 10/15cm including ramming, consolidation etc complete for all type of pipes of following sizes as per drawing and or as directed by Engineer.				
A	17.30.10	b) 600 mm internal diameter				
			100.00			
			100.00	Mtr	467.50	46750.00
5	R-17.18.	Providing at site, lowering & laying in trenches, aligning & jointing of RCC pipes NP4 class (with s/s ends) IS: 458 - 2003 (amended up to date) marked and pipes from 300 mm and upto 1800 mm manufactured through vertical / vibrated casting process at all depths with Rubber gaskets (EPDM/SBR) for sewer lines as per IS: 5382 (including cost of Rubber gaskets, lubricants) as per drawing, sectional hydro testing of the sewer pipe line (including cost and conveyance of water to site for testing) etc., complete as per specification and / or as directed by Engineer. Note : E/w to be measured and paid separately. Length of pipe shall be measured in between the outer wall of two manholes / Inspection chambers. Pipe in the manhole/inspection chamber's wall shall deemed to be included in the item of manhole/inspection chamber shall not be payable.				
	17.18.15	a) 600mm internal diameter	100.00			
			100.00	Mtr	3790.00	379000.00
6	R-25.1.1	Random rubble masonry with hard stone in foundation and plinth : Cement mortar 1:6 (1 cement : 6 coarse sand)				
			1.73			
		total	1.73			
		ded	-0.26			
			1.47	Cum	4245.00	6231.66
7	R-17.80.1	Supplying & fixing 560mm dia SFRC manhole frame & cover as per IS : 12592-2002 in existing manholes including grouting the frame in PCC M-15 complete in all respect as directed by the Engineer. HD-20	6.00	Nos	2685.00	16110.00
8	R-1.1.1	Carriage of Materials by mechanical transport including loading, unloading and stacking UPTO 5 KM : Earth				
			32.97			
			32.97			
			400.00			
			432.97	CUM	245.95	106488.97
9	R-30.35	Carriage of Materials by mechanical transport including loading, unloading and stacking UPTO 1.0KM : Earth	2667.03	Cum	152.02	405441.90

*Jm*

Item No.	Particulars	Qty.	Unit	Rate	Amount
4.4	Construction of embankment with approved material obtained from borrow pit with all lifts and leads, transporting to site, spreading, grading to required slope and compacting by vibratory roller 8-10 tonne to meet requirement of table 300-2 including cost of compensation for earth taken from private land complete as per MoRT&H specification clause 305. (Lead taken upto 5 km)	200.00	CUM	184.50	36900.00
4.5	Construction of embankment with approved materials deposited at site available from roadway cutting and excavation from drain and foundation of other structures, graded and compacting by vibratory roller 8-10 tonne to meet requirement of table 300-2 as per MoRT&H specification clause 305.	2667.03	CUM	77.50	206694.83
<b>Total</b>					<b>2302577.36</b>
				<b>SAY RS</b>	<b>23.03 Lac</b>

**Terms and Condition :-**

1. सभी प्रकार के कर (टैक्स) संवेदक द्वारा ही वहन किये जायेंगे।
2. कार्य स्थल पर श्रमिक व सामग्री की सुरक्षा की जिम्मेवारी संवेदक की होगी।
3. जी.सारणी में वर्णित कार्यों के अतिरिक्त व अधिक कार्य संवेदक द्वारा दी गई दरों के आधार पर
4. कार्य स्थल पर कार्य सम्बंधित सूचनाएं दर्शाने वाला बोर्ड संवेदक को स्वयं के स्तर पर लगाना होगा।
5. टंकण त्रुटी की अवस्था में सम्बन्धित रेट मान्य होगी।
6. कार्य करने से पूर्व एवं कार्य करने के पश्चात कार्य स्थल की फोटो/विडियोग्राफी सीडी आवश्यक रूप से कार्यालय में जमा कराने होंगे।
7. दोष निवारण अवधि नियमानुसार रहेगी।
8. दरें 4 माह तक मान्य रहेगी
9. शर्त निविदा स्वीकार नहीं होगी।
10. निष्पादन सुरक्षा राशि 10 प्रतिशत मय अनुबन्ध के जमा कराना होगा।



EXECUTIVE ENGINEER  
NAGAR NIGAM, JODHPUR.

I/We hereby agree to do the above work @ \_\_\_\_\_ Above/below the "G"

(Signature of Contractor)