

कार्यालय जोधपुर नगर निगम-दक्षिण

क्रमांक:- विकास/दक्षिण/2022-23/13७७

दिनांक :- ०7.०२.२०२३

सीमित निविदा सूचना

नगर निगम जोधपुर की ओर से निम्नलिखित सिविल कार्य हेतु निगम जोधपुर में सिविल कार्य में पंजीकृत अथवा अन्य समानान्तर विभाग में सिविल कार्य में पंजीकृत ए व एए श्रेणी संवेदको से सीमित निविदा के माध्यम से कोटेशन प्राप्त किये जाने है।

क्र. सं.	कार्य का नाम	अनु. लागत (लाखों में)	निविदा विक्रय व प्राप्ति की दिनांक
01	Railing and repairing work near Pt. Deendayal Upadhaye Stechu and park.	1.99	निविदा जारी होने की दिनांक २.२.२०२३ से दिनांक २.२.२०२३ को मध्याह्न ०१:०० बजे तक विक्रय की जायेगी तथा दिनांक २.२.२०२३ को मध्याह्न ०१:३० बजे प्राप्त की जायेगी।



अधिशायी अभियन्ता
जोधपुर नगर निगम-दक्षिण

दिनांक :- ०7.०२.२०२३

क्रमांक:- विकास/दक्षिण/2022-23/14७७ to 14०३

प्रतिलिपी :- सूचनार्थ एवं आवश्यक कार्यवाही हेतु।

1. निजी सचिव, आयुक्त, नगर निगम जोधपुर-दक्षिण।
2. सूचना पट्ट, जोधपुर नगर निगम उत्तर/दक्षिण।
3. श्री रामेश्वर गहलोत, प्रोग्रामर, नगर निगम जोधपुर दक्षिण को वास्ते
sppp.rajjasthan.gov.in पर अपलोड करने हेतु।



अधिशायी अभियन्ता
जोधपुर नगर निगम-दक्षिण

MUNICIPAL CORPORATION, JODHPUR (SOUTH)

GSCHEDULE

NT No. date
 Sr No.
 Earnest Money : Rs.
 Last Date of Sale :-
 CR No. Dated.
 Date of Receipt :-
 Copy issued to M/s

Name of work - Railing and Repairing work Near Pt. Deendayal Upadhyay Stechu and Park.

S.No.	Item	QTY	Unit	BASED ON BUIDP 2022	
				Rate in Rs.	Amount
1	Steel work welded in built up sections/ framed work including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required in gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.	1160.00	KG	117.50	136300.00
2	Providing and fixing Marble stone flooring table rubbed, 15-18 mm thick over 20mm (Av.) thick base of CM 1:4 (1 cement : 4 coarse sand) or slab in wal, steps, pillars, counters, jambs, shelves, sills etc laid over 12mm (Av.) thick base of CM 1:3 (1 cement : 3 coarse sand), jointing with white cement mortar 1:2 (1 white cement : 2 marble dust) with pigment to match the shade of the marble slab including grinding, rubbing and polishing complete. Makrana Adanga. Upto to 1500 Cm2 Tiles	10.00	SQM	1762.00	17620.00
3	Extra for Mirror polishing on marble work where ever required to give high gloss finish complete.	200.00	SQM	137.00	27400.00
4	Providing and fixing of precast concrete interlocking tiles of desired shape of M 30 grade manufactured from fully computerized automatic stationery hydraulic vibro pressed machine and fully computerized automatic batching plant of class A1/A2 as per BS 6717:2001. The CC interlocking paving blocks be laid on average 50mm. thick bed of coarse sand and the joint is to be filled with fine sand. Laying procedure on compacted sub-base as defined. Complete job is to be executed as per the instruction of Engineer incharge. The rates to be inclusive of all lead & Lifts etc. complete as per specifications. Tensile splitting strength, abrasion and braking load etc. as per BS 6717:2001, Grey cement.80mm thick	10.00	SQM	855.00	8550.00
5	Distemping with dry distemper of approved brand and manufacture (two or more coats) and of required shade on new work, over and including priming coat of whitening to give an even shade.	100.00	SQM	95.40	9540.00
Total				199410.00	
SAY RS				1.99 lacs	

Terms and Condition :-

1. सभी प्रकार के कर (टैक्स) सेवेदक द्वारा ही वहन किये जायेंगे।
2. कार्य स्थल पर श्रमिक व सामग्री की सुरक्षा की जिम्मेवारी सेवेदक की होगी।
3. जी.साल्गी में वर्णित कार्यों के अतिरिक्त व अधिक कार्य सेवेदक द्वारा दी गई दरों के आधार पर करवाये
4. कार्य स्थल पर कार्य संबंधित सूचनाएं दर्शाने वाला बोर्ड सेवेदक को स्वयं के स्तर पर लगाना होगा।
5. टंकण ड्यूटी की अवस्था में सम्बन्धित रेट मान्य होगी।
6. कार्य करने से पूर्व एवं कार्य करने के पश्चात कार्य स्थल की फोटो/विडियोग्राफी सीडी आवश्यक रूप
7. दौष निवारण अवधि नियमानुसार रहेगी।
8. दरें 4 माह तक मान्य रहेगी।
9. सवार्त निविदा स्वीकार नहीं होगी।

I/We hereby agree to do the above work @ _____ Above/below the "G" Schedule.



EXECUTIVE ENGINEER
 NAGAR NIGAM, JODHPUR.

(Signature of Contractor)