

18.0 Horizontal Centrifugal Pumps

Code No	Description	Unit	Rate
18.0.1	Supply, delivery at site with necessary packing, receiving, unloading, shifting, storing, installation, testing and commissioning of Horizontal Centrifugal Split Casting pumps with motor, CI casing and casing ring, SS 316 impeller, SS 410 Shaft and shaft sleeve, coupling guard, common base plate, foundation bolts etc. complete with all respect as per the specification.		
	P1.1: Q = 50 lps, H = 20 m	1 set	97500.00
	P1.2: Q = 50 lps, H = 30 m	1 set	143000.00
	P1.3: Q = 50 lps, H = 50 m	1 set	240500.00
	P1.4: Q = 50 lps, H = 70 m	1 set	357500.00
	P2.1: Q = 75 lps, H = 20 m	1 set	143000.00
	P2.2: Q = 75 lps, H = 30 m	1 set	222000.00
	P2.3: Q = 75 lps, H = 50 m	1 set	357000.00
	P2.4: Q = 75 lps, H = 70 m	1 set	487500.00
	P3.1: Q = 100 lps, H = 20 m	1 set	195000.00
	P3.2: Q = 100 lps, H = 30 m	1 set	292500.00
	P3.3: Q = 100 lps, H = 50 m	1 set	487500.00
	P3.4: Q = 100 lps, H = 70 m	1 set	715000.00
	P4.1: Q = 150 lps, H = 20 m	1 set	292500.00
	P4.2: Q = 150 lps, H = 30 m	1 set	487500.00
	P4.3: Q = 150 lps, H = 50 m	1 set	715000.00
	P4.4: Q = 150 lps, H = 70 m	1 set	855000.00
	P5.1: Q = 200 lps, H = 20 m	1 set	357000.00
	P5.2: Q = 200 lps, H = 30 m	1 set	585000.00
	P5.3: Q = 200 lps, H = 50 m	1 set	855000.00
	P5.4: Q = 200 lps, H = 70 m	1 set	1140000.00
	P5.1: Q = 300 lps, H = 20 m	1 set	585000.00
	P5.2: Q = 300 lps, H = 30 m	1 set	712500.00
	P5.3: Q = 300 lps, H = 50 m	1 set	1210000.00
	P5.4: Q = 300 lps, H = 70 m	1 set	1500000.00
	P6.1: Q = 400 lps, H = 20 m	1 set	715000.00
	P6.2: Q = 400 lps, H = 30 m	1 set	875000.00
	P6.3: Q = 400 lps, H = 50 m	1 set	1500000.00
	P6.4: Q = 400 lps, H = 70 m	1 set	1875000.00