



**Government of Rajasthan  
Office of Project Director**

**Rajasthan Urban Infrastructure Development Project (RUIDP)**

AVS Building, Jawahar Circle, JLN Marg, Jaipur - 302017

Tel No.: +91 141 2721966, Fax No.: +91 141 2721919

Email : mail@ruidp.gov.in, Web site : www.ruidp.gov.in

No. F3 (106) (33)/RUIDP/PMU/PH-II/SoR/2013/4894-4915 Date: 01.07.2014

**CORRIGENDUM -3**

As per powers delegated to undersigned CORRIGENDUM-3 is issued for RUIDP SOR September, 2013; applicable to cities of Rajasthan for RUIDP works. This CORRIGENDUM-3 will be considered as a modification to the original SOR September, 2013.

Encl: (1 Sheet).

*M 30.6.14*

**(Ambrish Kumar, IAS)  
Project Director  
RUIDP, Jaipur**

No. F3 (106)(33)/RUIDP/PMU/PH-II/SoR/2013/4894-4915 Date: 01.07.2014  
Copy submitted/forwarded to the following for information and necessary action:

1. PS to Addl. Chief Secretary, UDH & LSGD, GoR Jaipur
2. PS to Secretary, LSGD, GoR Jaipur
3. Accountant General, Audit/Inspection, Rajasthan, Jaipur
4. Administrator, Rajasthan State Agriculture Marketing Board, Pant Bhawan, Jaipur
5. Commissioner Jaipur Development Authority, Jaipur
6. Commissioner Rajasthan Housing Board, Jyoti Nagar, Jaipur
7. Executive Director, RUIDFCO, Jaipur
8. Director Local Bodies, Jaipur
9. Additional Project Director, RUIDP, Jaipur
10. Chief Engineer, PWD Rajasthan, Jaipur
11. Chief Engineer, PHED Rajasthan, Jaipur
12. Chief Engineer, Irrigation Rajasthan, Jaipur
13. Chief Engineer (Civil) Rajasthan Rajya Vidut Prasaran Nigam Ltd, Jaipur
14. Chief Engineer (HQ), UDH, UIT Kota
15. Financial Advisor RUIDP, Jaipur
16. Additional Chief Engineer (T), RUIDP Jaipur
17. Chief general Manager (P), RICCO, Udyog Bhawan, Jaipur
18. Additional Chief Engineer, PWD, Zone I, Jaipur(member T.C. RUIDP)
19. Additional Chief Engineer, Urban PHED, Jaipur(member T.C. RUIDP)
20. Additional Chief Engineer, Irrigation, Zone Jaipur(member T.C. RUIDP)
21. Superintending Engineer, DLB (member T.C. RUIDP)

*M*

**Project Director  
RUIDP, Jaipur**

**Corrigendum in SOR September, 2013:**

S. N.	Chapter Code	Item No.	Existing Unit	Modified Unit
1	12	<b>12.5</b> sub item no. 12.5.1, 12.5.2 12.5.3 & 12.5.4	Metre	<b>Sqm</b>
2		<b>12.6</b> sub item no. 12.6.1, 12.6.2, 12.6.3 & 12.6.4	Metre	<b>Sqm</b>

S. N.	Chapter Code	Item No.	Existing Rate/meter	Modified/Corrected Rate/meter
1.	20	20.2.1	231.00	<b>880.00</b>
2.		20.2.2	264.00	<b>1210.00</b>
3.		20.2.3	286.00	<b>1540.00</b>

S. N.	Chapter Code	Item No.	Existing Nomenclature	Modified/Corrected Nomenclature
1.	17	17.55	Construction of road side inspection chamber of "Type-A" with internal dia 450mm and depth of 900mm with 200 mm thick PCC M10 in foundation, 75mm thick PCC M15 flooring in slop, 230mm thick brick masonry/ RR stone masonry in CM (1:4), 20mm thick inside and outside plastering with CM (1:3), inside plaster finished with neat coat of cement, with "560 mm dia SFRC MD manhole frame and cover" embedded in 200mm thick PCC M20 grade concrete, refilling of Jhiri with watering and ramming including fixing 2 Nos. 110 OD uPVC pipe pieces (stiffness class SN 8) as per IS 15328 and plugging the same etc complete as per approved drawing and/or directed by Engineer.	Construction of road side inspection chamber of "Type-A" with internal dia 450mm and depth of 900mm with 200 mm thick PCC M10 in foundation, 75mm thick PCC M15 flooring in slop, 230mm thick brick masonry/ RR stone masonry in CM (1:4), 20mm thick inside and outside plastering with CM (1:3), inside plaster finished with neat coat of cement, with " <b>circular 450 mm dia precast RCC manhole cover and frame HD-20</b> " embedded in 200mm thick PCC M20 grade concrete, refilling of Jhiri with watering and ramming including fixing 2 Nos. 110 OD uPVC pipe pieces (stiffness class SN 8) as per IS 15328 and plugging the same etc complete as per approved drawing and/or directed by Engineer.

*[Handwritten Signature]*

*[Handwritten Signature]*  
PO (WS,1)

*[Handwritten Signature]*

*[Handwritten Signature]*  
SE(W)

*[Handwritten Signature]*  
REC'D