

Sub: Construction Management System: Circular – 64

Ref: Guidelines for execution of manhole and property connection up to property boundary in sewer line works under RUSDIP - (RUIDP - Phase II).

In the RUSDIP towns, works of laying sewer line are being executed. During laying sewer lines, it should be ensured that complete construction material for a section/line has been procured before excavation for the work of laying of sewer line. Work of manhole & laying of pipe for property connection in that section should be taken up simultaneously with laying of sewer line work. Due to non execution of work of sewer line, manhole and pipe for house property connection simultaneously, there is a lag in the hydro testing of sewer line and road restoration.

In this reference following guidelines should be followed by the IPIU for execution of sewer line work;

1. Executive Engineer, IPIU should ensure that before giving the layout for sewer line work in a particular lane, contractor should have all required material, manpower and resources.
2. It should be ensured that manhole is constructed and pipe for property connection upto property boundary is laid simultaneously with laying of sewer line.
3. It should be ensured that sewer line and manhole should be tested simultaneously.
4. It should also be ensured that after execution of work, road restoration work is completed and contractor leaves the lane only after clearing the site in all respect.

DSC & IPIU and particularly EE, IPIU as a head of the team shall be accountable & responsible for ensuring simultaneous work of sewer line, manhole & pipe for property connection with all road restoration work with quality standards.

This circular is equally applicable to all members of PMU, IPIU, IPMC & DSC.


(Vaibhav Galriya)
Project Director

Dated: 26.04.2012

F3 (106) (32)/RUSDIP/PMU/CMS/2007/1453-60

Copy to following for information and necessary action:

1. Addl. PD / CE (T)/ FA / Dy. PD (Adm.)/ Dy. PD (NLCP)/SE (Co-ord)/ SE (WW)/ (WS) / (Roads)/ (Bridges)/ PO (all)/ Sr. AO / All APOs / AAO/ PA to PD PMU, RUIDP, Jaipur.
2. Zone SE, RUSDIP, Jaipur/Jodhpur/Kota.
3. Executive Engineer, IPIU, RUSDIP, Alwar, Baran, Barmer, Bharatpur, Bundi, Chittorgarh, Churu, Dholpur, Jaisalmer, Jhalawar-Jhalarapatan, Karauli, Nagaur, Rajsamand, Sawai Madhopur, Sikar.
4. Team Leader IPMC, Jaipur/ DSC-I, Jaipur/ DSC-II, Jodhpur/ DSC-III, Kota, RUSDIP.
5. Dy. TL/ACM, DSC-I, Alwar/ Dholpur/ Karauli/ Sawai Madhopur, Dy. TL/ACM, DSC-II, Churu/ Jaisalmer/ Barmer/ Sikar and Dy. TL/ACM, DSC-III, Chittorgarh/ Rajsamand/ Bundi/ Baran, RUSDIP.
6. SE(UIDSSMT), RUIDP, to circulate and ensure compliance in the UIDSSMT works.
7. ACP, RUIDP, Jaipur to send by e-mail.


Chief Engineer (T)